

JUN 06 1996	<b>ENGINEERING DATA TRANSMITTAL</b>	Page 1 of 1 1. EDT <b>Nº 615398</b>
-------------	-------------------------------------	--

2. To: (Receiving Organization) Distribution		3. From: (Originating Organization) Data Assessment and Interpretation		4. Related EDT No.: N/A					
5. Proj./Prog./Dept./Div.: Tank 241-B-201/Waste Management/DAI/TWRS Technical Basis		6. Cog. Engr.: John M. Conner		7. Purchase Order No.: N/A					
8. Originator Remarks: This document is being released into the supporting document system for retrievability purposes.				9. Equip./Component No.: N/A					
				10. System/Bldg./Facility: 241-B-201					
11. Receiver Remarks: For release.				12. Major Assm. Dwg. No.: N/A					
				13. Permit/Permit Application No.: N/A					
				14. Required Response Date: 06/03/96					
15. DATA TRANSMITTED									
(A) Item No.	(B) Document/Drawing No.	(C) Sheet No.	(D) Rev. No.	(E) Title or Description of Data Transmitted	(F) Approval Designator	(G) Reason for Transmittal	(H) Originator Disposition	(I) Receiver Disposition	
1	WHC-SD-WM-ER-550	N/A	0	Tank Characterization Report for Single-Shell Tank 241-B-201	N/A	2	1	1	
16. KEY									
Approval Designator (F)		Reason for Transmittal (G)			Disposition (H) & (I)				
E, S, Q, D or N/A (see WHC-CM-3-5, Sec.12.7)		1. Approval 2. Release 3. Information 4. Review 5. Post-Review 6. Dist. (Receipt Acknow. Required)			1. Approved 2. Approved w/comment 3. Disapproved w/comment 4. Reviewed no/comment 5. Reviewed w/comment 6. Receipt acknowledged				
(G)	(H)	17. SIGNATURE/DISTRIBUTION (See Approval Designator for required signatures)						(G)	(H)
Reason	Disp.	(J) Name	(K) Signature	(L) Date	(M) MSIN	(J) Name	(K) Signature	(L) Date	(M) MSIN
2	1	Cog.Eng. J.M. Conner	<i>[Signature]</i>	6-5-96					
2	1	Cog. Mgr. J.G. Kristofzski	<i>[Signature]</i>	6-5-96					
		QA							
		Safety							
		Env.							
18.		19.		20.		21. DOE APPROVAL (if required)			
A.E. Young <i>[Signature]</i> 6-3-96 Signature of EDT Originator		N/A Authorized Representative Date for Receiving Organization		J.G. Kristofzski <i>[Signature]</i> 6-5-96 Cognizant Manager Date		Ctrl. No. <input type="checkbox"/> Approved <input type="checkbox"/> Approved w/comments <input type="checkbox"/> Disapproved w/comments			

BD-7400-172-2 (04/94) GEF097

BD-7400-172-1

## Tank Characterization Report for Single-Shell Tank 241-B-201

John M. Conner

Westinghouse Hanford Company, Richland, WA 99352  
U.S. Department of Energy Contract DE-AC06-87RL10930


EDT/ECN: EDT-615398 UC: 2070  
Org Code: 79400 Charge Code: N4G4D  
B&R Code: EW 3120074 Total Pages: 118


Key Words: Tank 241-B-201, Tank B-201, B-201, B Farm, Tank  
Characterization Report, TCR, Single-Shell

Abstract: This tank characterization report for Tank 241-B-201 was  
initially released as PNL-10100. This document is now being released as  
WHC-SD-WM-ER-550 in order to accommodate internet publishing.

TRADEMARK DISCLAIMER. Reference herein to any specific commercial product, process, or service by  
trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its  
endorsement, recommendation, or favoring by the United States Government or any agency thereof or  
its contractors or subcontractors.

Printed in the United States of America. To obtain copies of this document, contact: WHC/BCS  
Document Control Services, P.O. Box 1970, Mailstop H6-08, Richland WA 99352, Phone (509) 372-2420;  
Fax (509) 376-4989.

 6/6/96  
Release Approval Date



**Approved for Public Release**

# **Tank Characterization Report for Single-Shell Tank B-201**

P. G. Heasler  
K. M. Remund  
J. M. Tingey  
D. B. Baird  
F. M. Ryan  
Pacific Northwest National Laboratory

J. M. Conner  
Westinghouse Hanford Company

Date Published  
June 1996

Prepared for the U.S. Department of Energy  
Assistant Secretary for Environmental Management



**Westinghouse**  
**Hanford Company**

P.O. Box 1970  
Richland, Washington

Management and Operations Contractor for the  
U.S. Department of Energy under Contract DE-AC06-87RL10930

**Approved for Public Release; Distribution is Unlimited**

### Executive Summary

Tank 241-B-201 (hereafter referred to as B-201) is a 208,000 liter (55,000 gallon) single-shell waste tank located in the 200 East B Tank Farm at Hanford. Two cores were taken from this tank in 1991 and analysis of the cores was conducted by Battelle's 325-A Laboratory in 1992. Characterization of the waste in this tank is being done to support the *Hanford Federal Facility Agreement and Consent Order* (Tri-Party Agreement), Milestone M-44-05 (Ecology 1993).

Tank B-201, located in the 200 East Area B Tank Farm, was constructed in 1943 and put into use in 1947. The history of this tank is relatively straightforward, compared to other tanks. For its entire lifetime, B-201 was used to hold wastes from the 224 facility, a lanthanum fluoride-based separation process that discharged wastes containing low concentration fission products. Waste from the 224 facility was pumped into this tank, allowed to settle, and the liquid effluent was allowed to overflow into cribs (long trenches engineered to receive waste material disposed into the soil). This tank was retired from service in 1975, and in 1980 surveillance data indicated the tank leaked 4,500 liters (1,189 gallons). The tank was consequently interim stabilized in 1981. The tank presently consists of 110,000 liters (29,000 gallons) of sludge-like waste. Historically, there are no unreviewed safety questions associated with this tank and none were revealed by a review of the data from the latest core sampling event in 1991.

There were no difficulties encountered during the core sampling of this tank. Core recoveries were generally 100%, and an extensive set of analytical measurements was run on

---

the core composites. Core 26 was taken from riser 2 and core 27 was taken from riser 7 (see Figure A-1). Since core 26 was taken near a waste inlet/outlet (i.e., a place where the waste was frequently disturbed) and the core 27 was on the side of the tank far from the inlet, these two cores should represent the extremes of sampling conditions in the tank. In fact, the two cores exhibited many significant differences, and this core-to-core variability is the principal contributor to the uncertainty in the tank inventory estimates. For example, in the case of aluminum, the relative standard deviation (RSD) of the mean estimate is 74%, caused in large part by a core-to-core RSD of 102%.

The constituents found in highest concentration ( $> 10,000 \mu\text{g/g}$ ) in the B-201 core samples were water, bismuth, nitrate, sodium, silicon, manganese, lanthanum, iron, and calcium in descending order of concentration.

The results of the chemical analyses have been compared to the dangerous waste codes in the *Washington Dangerous Waste Regulations* (WAC 173-303). This assessment was conducted by comparing tank analyses against dangerous waste characteristics ("D" waste codes) and against state waste codes. The comparison did not include checking tank analyses against "U," "P," "F," or "K" waste codes, since application of these codes is dependent on the source of the waste and not on particular constituent concentrations. The results indicate that the waste in this tank is adequately described in the Dangerous Waste Permit Application for the Single-Shell Tank System; this permit is discussed in De Lorenzo et al. (1994).

Figure ES-1. Top View of Tank B-201.




Table ES-1. Engineering Data Summary of Tank B-201.

Tank Engineering Description	Tank Status as of 1994
<p>Type: Single-shell tank</p> <p>Construction: 1943-1944</p> <p>In-Service: 1947</p> <p>Out of Service: 1975</p> <p>Diameter: 6.1 m (20 ft)</p> <p>Depth: 7.6 m (25 ft)</p> <p>Nominal Capacity: 208,000 L (55,000 gal)</p> <p>Bottom Shape: Dished</p> <p>Hanford Coordinates: N45537.5, W52727.5</p> <p>Ventilation: Passive</p>	<p>Watch List: None</p> <p>Interim Stabilized: 1981</p> <p>Interim Isolated: 1981</p> <p>Contents: 224 waste*</p> <p>Tank Integrity: Assumed leaker (1980) (4,500 L)</p>

\*Non-complexed waste.

Table ES-2. Inventory Summary for Tank B-201.

Physical Properties of Waste			
Total Waste:	110,000 L (29 000 gal)	Supernate Volume:	3,800 L (1,000 gal)
Drainable Inter. Liquid:	11,400 L (3,000 gal)	Density:	1.25 g/mL
H <sub>2</sub> O Average:	60.6%	Temperature Average:	17 °C (63 °F)
pH:	8.53	Maximum Exotherm:	No Exotherms
Heat Load:	0.006 kW		
Chemical Properties of Waste			
Bismuth:	13,000 kg (9.45 wt%)	Calcium:	1,670 kg (1.22 wt%)
Nitrate:	6,770 kg (4.93 wt%)	Fluoride:	800 kg (0.58 wt%)
Sodium:	5,240 kg (3.82 wt%)	Potassium:	797 kg (0.58 wt%)
Silicon:	2,770 kg (2.02 wt%)	Phosphorus:	748 kg (0.55 wt%)
Manganese:	2,630 kg (1.92 wt%)	TOC:	71 kg (5.18e-02 wt%)
Lanthanum:	2,070 kg (1.51 wt%)	TIC:	287 kg (0.21 wt%)
Iron:	1,840 kg (1.34 wt%)		
Radionuclides in the Waste			
Total Plutonium:	156 Ci	Strontium-90:	287 Ci
Cesium-137:	110 Ci	Total Uranium	21.4 kg (1.56e-04 wt%)

---



---

**TABLE OF CONTENTS**

1.0 INTRODUCTION .....	1-1
1.1 PURPOSE .....	1-1
1.2 SCOPE .....	1-1
2.0 HISTORICAL TANK INFORMATION .....	2-1
2.1 TANK DESCRIPTION .....	2-1
2.2 PROCESS KNOWLEDGE .....	2-1
2.3 SURVEILLANCE DATA .....	2-3
2.4 TANK STATUS .....	2-5
3.0 TANK SAMPLING OVERVIEW .....	3-1
3.1 CORE SAMPLING .....	3-1
3.2 ADDITIONAL TANK SAMPLING .....	3-3
4.0 SAMPLE HANDLING AND ANALYTICAL SCHEME .....	4-1
4.1 WASTE DESCRIPTION .....	4-1
4.2 HOLDING TIME CONSIDERATIONS .....	4-4
4.3 SAMPLE PREPARATION AND ANALYTICAL METHODS .....	4-4
5.0 ANALYTICAL RESULTS AND WASTE INVENTORY .....	5-1
5.1 CHEMICAL ANALYSES AND RADIOLOGICAL DETERMINATIONS .....	5-1
5.2 PHYSICAL MEASUREMENTS .....	5-12
5.2.1 Physical and Rheological Properties .....	5-13
5.2.2 Energetics .....	5-14
5.2.3 Particle Size Analysis .....	5-15
5.3 HEAT LOAD ANALYSIS .....	5-16
6.0 INTERPRETATION OF ANALYTICAL RESULTS .....	6-1
6.1 TANK WASTE PROFILE .....	6-1
6.2 WASTE SUMMARY AND CONDITIONS .....	6-4
7.0 STATISTICAL QUALITY ASSURANCE TESTS .....	7-1
7.1 MASS AND CHARGE BALANCE .....	7-1
7.2 HOMOGENIZATION TESTS .....	7-4
7.3 EVALUATION OF SPIKES AND BLANKS .....	7-6
7.3.1 Blank Measurements .....	7-7
7.3.2 Spike Measurements .....	7-8
7.3.3 Quality Assurance Flags .....	7-10
8.0 CONCLUSIONS AND RECOMMENDATIONS .....	8-1

---



---



9.0 REFERENCES .....	9-1
----------------------	-----

10.0 BIBLIOGRAPHY .....	10-1
-------------------------	------

## APPENDIXES

A TANK ENGINEERING DATA AND WASTE SUMMARY .....	A-1
B COMPOSITE ESTIMATES AND VARIABILITY SUMMARY .....	B-1
C SEGMENT-LEVEL ESTIMATES AND VARIABILITY SUMMARY .....	C-1
D RAW DATA SET SUMMARY .....	D-1
E RHEOLOGICAL PROPERTIES TABLES AND PLOTS .....	E-1

## LIST OF FIGURES

2-1 Tank Waste Level Summary for B-201 .....	2-3
2-2 Thermocouple Data for B-201 .....	2-4
4-1 Segment Photographs for Core 26 .....	4-2
4-2 Segment Photographs for Core 27 .....	4-3
4-3 Sample Preparation Flowchart .....	4-4
5-1 RSD Distributions for Variance Components Calculated from the Composite-Level Data .....	5-8
5-2 Residuals Plot for ICP Acid Digestion Aluminum Analysis .....	5-11
6-1 RSD Distributions for Variance Components Calculated from the Segment-Level Data .....	6-7
7-1 Boxplots of Blank/Actual for Each Analytical Method ( <DL Measurements Excluded) .....	7-8
7-2 Boxplots % Recovery Calculated from Spike Measurements .....	7-9

---



---

**LIST OF TABLES**

2-1	Estimated Composition of B-201 Contents . . . . .	2-2
3-1	Actual Percent Recovery in B-201 . . . . .	3-2
3-2	Historical Core Sample Analytical Data for B-201 . . . . .	3-3
4-1	Sample Preparation and Analytical Methods Used on B-201 Samples . . . . .	4-6
5-1	Summary of B-201 Analytical Result Counts . . . . .	5-1
5-2	Summary of the Composite Level Results for Anions, Metals, Organics, and Radionuclides . . . . .	5-2
5-3	Analytes Grouped According to Concentration Differences Between Cores . . . . .	5-9
5-4	Composite Values Omitted from Analyses as Suspect . . . . .	5-10
5-5	Summary of Core 26 Physical Measurements . . . . .	5-12
5-6	Weight Percent Solids . . . . .	5-13
5-7	Core 27 Differential Scanning Calorimetry Thermal Measurements . . . . .	5-15
5-8	Particle Size Distribution for Core 27 . . . . .	5-16
5-9	Radionuclide Inventory and Projected Heat Load . . . . .	5-16
6-1	Available Segment-Level Measurements . . . . .	6-2
6-2	Summary of RSD Values . . . . .	6-3
6-3	Analytes Classified by Dominant RSD . . . . .	6-4
6-4	Comparison of Mean Tank Estimates (Historical versus Sampling Results) . . . . .	6-5
6-5	Alpha and Beta Energy Checks . . . . .	6-6
7-1	Mass/Charge Balance for Metals . . . . .	7-1
7-2	Anions with postulated Oxy-anions . . . . .	7-2
7-3	Phosphate Solubility . . . . .	7-3
7-4	Summary of Mass/Charge Balance . . . . .	7-3
7-5	Homogenization Test Results . . . . .	7-5
7-6	Illustration of Contamination Problem for ICP fusion on Core 26 . . . . .	7-6
7-7	Summary of Blank Measurements . . . . .	7-7
7-8	Summary of Recoveries Calculated from Spike Measurements . . . . .	7-10

---



---

**LIST OF TERMS**

AA	atomic absorption
ANOVA	analysis of variance
CVAA	cold vapor atomic absorption
GC	gas chromatography
GEA	gamma energy analysis
HAS	Hanford Analytical Services
ICP	inductively coupled plasma atomic emission spectrometry
LANL	Los Alamos National Laboratory
PNNL	Pacific Northwest National Laboratory
QA	quality assurance
RPD	relative percent difference
RSD	relative standard deviation
SAL	Shielded Analytical Laboratory
SST	single-shell tank
TCLP	toxicity characteristic leach procedure
TIC	total inorganic carbon
TOC	total organic carbon
TRAC	Track Radioactive Components (model)
Tri-Party Agreement	Hanford Federal Facility Agreement and Consent Order
WHC	Westinghouse Hanford Company

### **Acknowledgements**

It is appropriate to acknowledge individuals that made important contributions to this report. Brett Simpson (Westinghouse Hanford Company) provided many valuable comments and recommendations that helped prepare this report. Stacey Hartley spent many hours preparing this report for its final edition. Daryl Baird wrote several computer programs that helped in statistical analysis of the B-201 data. We also appreciate the help of Chris Brevick (ICF Kaiser Hanford Company) and Todd Brown (Westinghouse Hanford Company) for providing much of the historical information that was needed for this report.

This page intentionally left blank.

## 1.0 INTRODUCTION

Analysis was conducted on materials obtained from tank B-201 to complete the *Hanford Federal Facility Agreement and Consent Order* (Tri-Party Agreement), Milestone M-44-05 (Ecology 1993) to sample, analyze, and report on 20 tanks. Other objectives that these measurements and inventory estimates support are as follows:

- Obtain estimates of both the concentration and total quantity of key analytes relating to safety issues such as organics and radionuclides.
- Provide input to risk-assessment-based decisions for disposal of the waste.
- Implement physical property measurements such as rheology, bulk density, and particle size.

These measurements are necessary for the design and fabrication of retrieval, pretreatment, and final waste disposal systems.

### 1.1 PURPOSE

The purpose of this report is to characterize the waste in single-shell tank (SST) B-201. "Characterization" includes the determination of the physical, chemical (e.g., concentrations of elements and organic species), and radiological properties of the waste. These determinations are made using analytical results from B-201 core samples as well as historical information about the tank. The main objective is to determine average waste properties; but in some cases, concentrations of analytes as a function of depth were also determined.

This report also consolidates the available historical information regarding tank B-201, arranges the analytical information from the recent core sampling in a useful format, and provides an interpretation of the data within the context of what is known about the tank.

### 1.2 SCOPE

The waste properties are determined from core samples, which were chemically analyzed by the Pacific Northwest National Laboratory (PNNL, 325-A Laboratory). Additional relevant information on the waste has been compiled from historical sources. Types of historical information that are routinely checked include:

- Past sampling events
- Routine tank surveillance measurements
- Tank transfer records.

This historical information has been reviewed and compared with the laboratory data to help interpret the laboratory data correctly. However, the characterization estimates presented are derived from the laboratory data unless otherwise indicated. The laboratory data is considered to provide the most authoritative description of the tank waste.

The minimum required sampling and analysis was performed on tank B-201. This sampling is intended to determine mean concentrations (through composite analysis) and is thus intended to meet process design characterization objectives for waste treatment. Process design generally requires knowledge of total inventories. However, a few measurements were made to predict the spatial distribution of specific analytes in the tank.

---

---

## 2.0 HISTORICAL TANK INFORMATION

Since 1944, underground storage tanks in Hanford's 200 Areas have been used to store radioactive waste generated by processing plants and laboratories on the Hanford Site. A study of waste management operation records yields information about the process waste types transferred into a tank and the physical state of the waste. By reviewing the plant effluent stream composition, transfer records, and the subsequent history of the service life of a tank, hypotheses about the expected contents of the tank can be made.

The B Tank Farm is located in the 200 East Area and was constructed during 1943 and 1944. The B Tank Farm is one of the original four tank farms (B, C, T, and U) made up of SSTs. There are 16 waste tanks in B Farm. Four tanks (B-201 to B-204) have a nominal capacity of 208,000 liters (55,000 gallons). Tanks B-202, B-203, and B-204 are connected together via tie lines whereas tank B-201 is not. The remaining 12 tanks (B-101 to B-112) have a capacity of 2,006,000 liters (530,000 gallons).

### 2.1 TANK DESCRIPTION

A summary of the basic design for tank B-201 is presented in Appendix A. As can be seen from the schematics presented in the appendix, B-201 is a small tank with a capacity of 208,000 liters. The tank is buried under approximately 2 meters (6.5 feet) of earth for shielding purposes and is not connected in cascade or by tie lines with any other tanks. The tank was classified as a leaker in 1980 and it is estimated to have leaked approximately 4,500 liters (1,189 gallons) of waste.

### 2.2 PROCESS KNOWLEDGE

The process history for this tank is relatively straightforward. Tank B-201, as well as the other three 208,000-liter tanks in B Farm (B-202 through B-204), received waste from essentially one source, the  $LaF_3$  Plutonium Concentration Process (one of the final steps in the Bismuth Phosphate Process) located in the 224 Building. This "224-waste" has a very low radionuclide content (low enough to permit ground disposal). When tank B-201 was in operation, the waste from the 224 Building was run into the tank and the solids were allowed to settle out. The liquid waste was then directed into a crib, a long trench engineered to receive wastes for disposal into the soil. An estimated 110,000 liters (29,000 gallons) of this waste is currently in the tank and its historical composition is as described in Table 2-1. These estimates were derived by Los Alamos National Laboratory (LANL) and are tabulated in Brevick 1994. The numbers given in Table 2-1 are the estimated composition of the waste in B-201, rather than the composition of the waste stream from the 224 Building.



Table 2-1. Estimated Composition of B-201 Contents.

Analyte	M	$\mu\text{g/g}$	Analyte	M	$\mu\text{g/g}$
Sodium	1.906	39018	Free Hydroxide	0.015	230
Nitrate	1.292	71304	Carbonate	0.000	0
Hydroxide	0.556	8419	Sulfate	0.000	0
Fluoride	0.303	5132	Calcium	0.000	0
Potassium	0.259	9014	Chloride	0.000	0
Oxalate	0.214	16800	Nitrite	0.000	0
Phosphate	0.201	17001	Acetate	0.000	0
Bismuth	0.159	29581	Uranium	0.000	0
Manganese	0.117	5770	TOC	0.458 wt%	4580
Chromium	0.023	1068			
Plutonium		0.964 $\mu\text{Ci/g}$	Density	1.123 g/mL	
Cesium		0.000 $\mu\text{Ci/L}$	Water	80.140%	
Strontium		0.000 $\mu\text{Ci/L}$			

Based on LANL's historical tank composition estimates, it is expected that the waste in B-201 should be very similar to the waste in B-202, B-203, and B-204.


The Hanford Works Monthly Reports for February and March of 1948 (HW-9191 and HW-9595) indicate that B-201 received cell drainage waste from cell 5, tank 6 in B Plant (i.e., 5-6 waste). When any of the subprocesses of the Bismuth Phosphate Process boiled over, the waste drained to cell 5, tank 6. Since the cell could have received waste from several of these subprocesses, little is known about the composition of this waste type. The amount of 5-6 waste that was received by B-201 is also unknown. No attempt was made to determine the impact that the 5-6 waste had on the tank contents.

B-201 started receiving waste from the 224 Building in 1947. By the end of the first quarter of 1952, B-201 had received at least 206,000 liters (54,500 gallons) of 224-waste, and was actively cascading into a crib. In the second quarter of 1958, the solid portion of the waste was estimated to be 106,000 liters (28,000 gallons). In the second quarter of 1971, 83,000 liters (22,000 gallons) of supernate were transferred out of tank B-201 to tank B-106. During 1974 and 1975, five smaller supernate transfers (4,000 to 23,000 liters [1,057 to 6,076 gallons]) were made from B-201 to B-109. In the fourth quarter of 1974, 15,000 liters (3,963 gallons) of water were added to the tank and in the third quarter of 1975, B-201 was removed from service.

The total tank waste volume remained basically constant at 110,000 liters from the third quarter of 1975 to the present time, with the exception of the assumed leak of

4,500 liters in 1980. The total volume of solids in the tank is 106,000 liters and the total volume of supernate liquid is approximately 3,800 liters (1,004 gallons). Jungfleisch and Simpson 1993, also obtained tank content estimates for B-201 (via the Track Radioactive Components model [TRAC]). However, all of the estimates supplied by TRAC were zero, and therefore, TRAC results are not included here for comparison to the LANL historical estimates. (See Figure 2-1).

Figure 2-1. Tank Waste Level Summary for B-201.



## 2.3 SURVEILLANCE DATA


Each of the 177 underground tanks at the Hanford Site is routinely monitored for changes in supernate levels, solid waste levels, and temperature readings. A monthly surveillance report lists the results of this monitoring and the status of each tank (e.g., watch lists, leak status, unusual events).

A possible discrepancy can be seen in the data between 1952 and 1972. The solids levels reported over this time period rise as high as 7.3 meters (204,000 liters). It is doubtful that the solids level ever rose above 3.8 meters (approximately 110,000 liters). This is due to the fact that approximately 117,000 liters (30,908 gallons) of supernate were

transferred from B-201 to B-106 and B-109 between 1971 and 1974 (Anderson 1990). After these transfers, the reported levels for supernate and solids dropped to the same level now observed (110,000 liters). Given that supernate was all that was removed from the tank, it is reasonable to assume that the solids level never rose above 3.8 meters. Another point that adds credence to the last statement is that the reported solids levels during 1958 and 1959 dropped to approximately 110,000 liters, even though no tank transfer activity is reported during that same time period.

Figure 2-2 is a plot of the B-201 temperature data recorded from 1975 to the present. With the exception of a group of readings in July 1989, the temperatures have remained relatively stable over time. Note that there are no recorded temperature readings from 1980 through 1988. In the last group of data from 1990 to the present, temperatures deviate from 17 °C (63 °F) by  $\pm 5.5$  °C ( $\pm 10$  °F). Within a given year during this time period, temperatures deviate from the average reading by  $\pm 3$  °C ( $\pm 6$  °F). The range of temperatures measured in B-201 is not high enough to warrant any concern about high heat evolution.

Figure 2-2. Thermocouple Data for B-201.



## 2.4 TANK STATUS

B-201 is presently not on any watch list and has no unreviewed safety issues. B-201 is an interim isolated tank, which means that all access to the tank not required for long-term surveillance has been sealed in a way that provides at least one barrier to the inadvertent addition of liquid. This tank is also interim stabilized. This means that B-201 is an inactive waste storage tank, and that as much of the free liquid as possible has been removed with a salt well pump. B-201 was put on the assumed leaker list after an observed drop in the waste surface level (approximately 4,500 liters) was detected in 1980.

This page intentionally left blank.

---

### 3.0 TANK SAMPLING OVERVIEW

This section describes the latest tank B-201 core sampling event (1991) and another core sampling event in 1978. For the 1991 sampling of tank B-201, details are given about the core sampling equipment, the sampling process, the location of samples taken from the tank, the sample recoveries, and the transfer of the core samples to the 325-A Laboratory.

#### 3.1 CORE SAMPLING

All Hanford waste tanks are underground tanks, usually buried under 2 meters (6.5 feet) of earth. Consequently, access to the waste is limited to existing risers, as illustrated in Appendix A. Special core sampling equipment, which is mounted on trucks, is used to take cores from the tank. During sampling, the truck is positioned over the desired riser and a "drill-string" containing the sampler is lowered into the tank. Two types of samplers are used at Hanford, push mode and rotary mode. The rotary mode samplers are much more effective in producing a complete sample of the waste (a rotary mode sampler can actually be used in push or rotary mode). However, the rotary mode sampler takes more time to set up, and there are some safety concerns associated with it (e.g., generation of heat at the drill bit and potential ignition of the waste). Therefore, push mode sampling is used whenever possible. Since the waste was expected to be relatively soft, push mode sampling was used in tank B-201.

Several factors enter into the decision of which risers to sample. When possible, samples are taken from risers that are widely spaced, usually on opposite sides of the tank. This choice provides some information on the lateral variation of the waste.

The sampler is constructed of stainless steel and is 48 cm (19 in.) long, with a 2.2 cm (7/8 in.) inside diameter, and has a volume of 187 mL. The sampler is fitted with a piston inside the cylindrical sample reservoir to control entry of the waste. As the drill string is lowered, the piston recedes from the sample reservoir and creates a partial vacuum that pulls the sample into the waste column. The sampler fits into a 5-cm (2-in.) drill pipe fitted with a blunt drill bit. After each segment is filled, the sampler is extracted from the drill pipe and another sampler is inserted. The drill string is then lowered another 48 cm (19 in.).

Some deficiencies associated with the sampler can have an impact on the representativeness of the sample. For example, because of the location of the risers, the sampler cannot extract the waste in the dished portion of the tank. Since the waste at the bottom of the tank may be significantly different from the rest, this can cause an important bias. Also, the sampler sometimes gets plugged and may gather much less than the standard 48 cm sample. Percent recovery estimates on a core or segment basis, express how completely the material has been sampled.

After a segment is captured by the sampler, it is sealed within a stainless steel liner and placed in a shipping cask. The casks are transported to the analytical laboratory for analysis and storage.

Two core samples were taken from tank B-201 at opposite ends of the tank in July, 1991 (core 26) and August, 1991 (core 27). Core 26 was taken through riser 2, which is near the waste inlet pipe. Core 27 was taken through riser 7. The strategy behind this selection of risers is simple; since the tank history indicates that the tank was used to settle solids from 224-waste and that this waste has not been disturbed by sluicing or by any tank transfers, the coarser solids should have settled out at core 26 and the finer at core 27. The two cores should therefore provide us with estimates of the extremes occurring in the waste. Ideally, the waste make-up between the two cores should vary in a linear fashion. If these assumptions concerning the waste are correct, these core locations should be optimal for producing an estimate of average waste make-up.

The waste in the tank is relatively deep (4 meters [13 feet]). In both cores, 8 segments were required to produce a complete column of the waste. Segment 1 is taken from the top of the waste, and segment 8 is a bottom sample.

In this tank, there were no recovery problems, and the sampler recovered essentially 100% of the core and segment samples. Segment 1 of core 26 has the lowest recovery, 65%. While this may seem low, the typical sampling protocol is to only partially fill the first segment of a sample, so that the rest of the waste column can be divided into whole segments. In fact, the planned recovery for this segment was 70%. The planned recovery for all other segments was 100%. Table 3-1 presents the percent recoveries achieved, along with the planned recovery for the first segment.

Table 3-1. Actual Percent Recovery in B-201.

Segment	Core 26	Core 27
1	65%/70%*	100%/100%*
2	95%	100%
3	100%	100%
4	100%	100%
5	100%	100%
6	100%	100%
7	100%	100%
8	100%	100%

\*Actual/Planned.

The sample casks were transported to the 325-A Laboratory for extrusion and characterization analysis. The 325-A Laboratory is operated by Battelle-PNNL in the 300 Area of the Hanford Site. Core 26 segments 1, 2, and 3 were delivered to the 325-A Laboratory on July 25, 1991; core 26 segments 7 and 8 were delivered on July 29, 1991; core 26 segments 4, 5, and 6 were delivered on July 30, 1991; core 27 segments 1, 2, and 3 were delivered on August 5, 1991; core 27 segments 4, 5, and 6 were delivered on August 7, 1991; and core 27 segments 7 and 8 were delivered on August 8, 1991.

### 3.2 ADDITIONAL TANK SAMPLING

In 1978, core samples were taken from all four of the 55,000-gallon tanks in B Tank Farm (B-201, B-202, B-203, and B-204). There is no information indicating where the core samples were taken within the tanks. These core samples were sent to the Chemical Sciences Group for characterization (Horton 1978).

The chemists noted that the core samples were black in color and had the consistency of soft grease. There is no information about core recovery percentages. However, personnel who operated core sampling equipment during that time period indicated that the equipment operated reasonably well in the type of waste described by the chemists. Table 3-2 contains the analytical results from the core sample taken from B-201 in 1978. The analytical results reported for the other three tanks are similar to the B-201 results. A comparison of the results from these samples to the historical estimates and the analytical results from the 1991 core sampling event will follow in Section 5.1.

Table 3-2. Historical Core Sample Analytical Data  
for B-201. (2 pages)

Analyte	Water Soluble	Acid (Fusion)
Al	0.05%	1.0%
Bi <sup>3+</sup>	<0.005%	3.8%
CO <sub>3</sub> <sup>2-</sup>	3.3%	NR
CrO <sub>4</sub>	0.05%	NR
Cl <sup>-</sup>	0.01%	NR
Fe	<0.0002%	1.8%
Hg	0.05%	NR
K	0.3%	NR
La <sup>3+</sup>	<0.003%	1.3%
Mn	<0.003%	NR
Ni <sup>2+</sup>		0.1%
NO <sub>2</sub>	0.004%	NR



Table 3-2. Historical Core Sample Analytical Data  
for B-201. (2 pages)

Analyte	Water Soluble	Acid (Fusion)
NO <sub>3</sub> <sup>-</sup>	3.3%	NR
Na <sup>+</sup>	2.8%	NR
OH <sup>-</sup>	0.6%	NR
PO <sub>4</sub> <sup>3-</sup>	0.05%	1.1%
SO <sub>4</sub> <sup>2-</sup>	<0.01%	<0.06%
SiO <sub>2</sub> <sup>2-</sup>	0.05%	0.3%
U	7.41E-06 g/g	1.05E-05 g/g
Pu	<1.29E-10 g/g	5.00E-05 g/g
Am	5.69E-12 g/g	1.33E-09 g/g
<sup>89+90</sup> Sr <sup>2+</sup>	2.10E-03 $\mu$ Ci/g	2.70 $\mu$ Ci/g
<sup>137</sup> Cs <sup>+</sup>	0.05 $\mu$ Ci/g	0.059 $\mu$ Ci/g
<sup>155</sup> Eu	NR	0.028 $\mu$ Ci/g
Ce	NR	0.016 $\mu$ Ci/g
Water Solubility	NR	23.0%
Bulk Density	NR	1.37 g/cc
Percent Water		72.2%

NR: Not Reported

---

## 4.0 SAMPLE HANDLING AND ANALYTICAL SCHEME

The sample handling and sample breakdown process and the analyses performed on each portion of the waste are described in this section. These analyses were performed on two core samples from tank B-201, core 26 and core 27. Each core sample consisted of eight 48-cm (19-in.) segments. The segments are numbered from 1 at the top of the core sample down to number 8 at the bottom.

### 4.1 WASTE DESCRIPTION

Eight segments of material from core 26 were received and extruded at PNNL's High-Level Radiochemistry Facility (325-A Hot-Cell Facility). Recoveries of 100% were achieved for all segments except segment 1 (65% recovery) and segment 2 (95% recovery). Segment 1 contained 57 mL of drainable liquid. The mass of the drainable liquid was 55.7 g and the density was 1.0 g/mL. No other segments from core 26 contained drainable liquids. The first portion of the drainable liquid to be extruded was tan to gray in color. This liquid was followed by a dark brown liquid. All of the drainable liquid was opaque. The solids obtained from segments 1 and 2 were sticky dark brown sludges which held their shape upon extrusion from the sampler. The consistency of the solids from these two segments varied from soft at the top to crumbly at the bottom of segment 2. The remainder of the sludge (segments 3 through 8) had a smooth texture, but extruded in chunks. The color of the core material gradually changed from dark brown to black as a function of the sample's depth in the tank. Segments 3 and 4 were dark brown to charcoal in color, while segments 5 through 8 were charcoal to black. The core material contained a significant amount of moisture, and in some spots in segment 7 it appeared that there were small pockets (less than 1 mL) of liquid trapped in the sludge.

Eight segments of material from core 27 were received and extruded. Recoveries of 100% were achieved for each of the segments. The majority of the core was a black moist sludge which held its shape upon extrusion. The core material contained a significant amount of moisture, but no drainable liquids were obtained. The top 5 to 7.6 cm (2 to 2.5 in.) of the core were dark brown, and the remainder of the core was shiny black. The core material was fairly stiff except for the top 2.5 cm (1 in.) of segments 2, 3, 4, and 5, which flowed upon extrusion.

Each segment from both cores was photographed in the extrusion tray. Figure 4-1 shows the segments for core 26 and Figure 4-2 shows the segments for core 27. For core 26, segments 1 through 8 are labeled 91-042 through 91-049, respectively. For core 27, segments 1 through 8 are labeled 90-050 through 90-057, respectively.

Figure 4-1. Segment Photographs for Core 26.





Figure 4-2. Segment Photographs for Core 27.




## 4.2 HOLDING TIME CONSIDERATIONS

No attempt was made to meet the holding times for these samples. The samples were received from Westinghouse Hanford Company (WHC) on August 8, 1991. Analyses were not started until January, 1992. This delay was due to waste disposal issues in the 325 Building.

## 4.3 SAMPLE PREPARATION AND ANALYTICAL METHODS

Figure 4-3 contains a flowchart of the steps taken by the 325-A Laboratory to analyze tank core samples.

Figure 4-3. Sample Preparation Flowchart.



---

Each of the eight segments from cores 26 and 27 were homogenized. Segments 3 and 7 from core 26 and segments 3 and 6 from core 27 were subsampled for the homogenization test analyses. These subsamples were acid digested and analyzed by two methods: inductively coupled plasma atomic emission spectroscopy (ICP), and gamma energy analysis (GEA).

The core 26 relative percent differences (RPD) for the sample and duplicate within the top and bottom of each segment are significantly higher than normal, indicating either insufficient homogenization, substantial sample heterogeneity, or inadequate subsampling. In general, for both segments from core 26, the "bottom" samples have higher concentrations of most analytes than the "top" samples. This may be caused by settling prior to subsampling. Based on numerous previous homogenization tests of the Hanford tank wastes, it has been determined that fusion preparations provide more consistent and quantitative results than acid digestion; therefore, further homogenization tests (e.g., on core composites) will use fusion preparations.

Typical RPDs of 10 to 20% for many duplicate pairs are marginally acceptable; however, these high homogenization RPDs potentially compromise the accuracy of the full suite of characterization analyses performed on the core composites 1 and 2. That is, the accuracy of any "single" analysis is biased by the inability to obtain a truly representative sampling from the blended composites. The homogenization tests are discussed in detail in Section 7.2.

In addition to these subsamples, two core composites were produced from the eight homogenized segments from each core. Homogenization test samples for the four core composites were prepared by caustic fusion and analyzed. Caustic fusion was used to prepare the samples rather than acid digestion, for reasons previously noted.

Each of the eight segments from core 27 were homogenized. Subsamples from segments 3 and 6 were prepared by acid digestion and analyzed by ICP and GEA. The homogenization test results indicated that the homogenization was insufficient. The segments were reblended and subsampled for preparation and analysis in the same manner as before. It was noted by the analyst during the preparation of the core 27 sludge that it had a greasy appearance. It was further noted that during acid digestion of the homogenization check sample, a white precipitate formed when hydrochloric acid was added. No precipitate was present while the sample was in a nitric acid media. Hydrofluoric acid and oxalic acid were added to the digestate and achieved total dissolution.

Similarly, two core composites were produced from the eight homogenized segments of core 27. Homogenization test samples from both composites were again prepared by caustic fusion.

The homogenized samples from cores 26 and 27 were prepared in the Shielded Analytical Laboratory (SAL), and included homogenization test samples and two core composites for each core. Due to the low level of radioactivity associated with the sludge from tank B-201, many of the analytical preparations were completed in the 325-A Laboratory (not the SAL).

Table 4-1 lists the preferred methods used to assay tank B-201 samples for the suite of requested analyses. For each analyte, the method listed as preferred produces the best estimate of concentration of that particular constituent.

Table 4-1. Sample Preparation and Analytical Methods Used on B-201 Samples. (2 pages)

Analyte	Sample Prep.	Preferred Method	Analyte	Sample Prep.	Preferred Method
Aluminum	A,F,W	ICP:A	Antimony	A,F,W	ICP:A
Arsenic	A,F,W	ICP:A	Barium	A,F,W	ICP:A
Bismuth	A,F,W	ICP:F	Beryllium	A,F,W	ICP:A
Boron	A,F,W	ICP:A	Cadmium	A,F,W	ICP:A
Calcium	A,F,W	ICP:A	Cerium	A,F,W	ICP:A
Chromium	A,F,W	ICP:A	Cobalt	A,F,W	ICP:A
Copper	A,F,W	ICP:A	Dysprosium	A,F,W	ICP:A
Europium	A,F,W	ICP:A	Gadolinium	A,F,W	ICP:A
Iron	A,F,W	ICP:F	Lanthanum	A,F,W	ICP:A
Lead	A,F,W	ICP:A	Lithium	A,F,W	ICP:A
Magnesium	A,F,W	ICP:A	Manganese	A,F,W	ICP:A
Molybdenum	A,F,W	ICP:A	Neodymium	A,F,W	ICP:A
Nickel	A,F,W	ICP:A	Palladium	A,F,W	ICP:A
Phosphorus	A,F,W	ICP:F	Potassium	A,F,W	ICP:A
Rhodium	A,F,W	ICP:A	Ruthenium	A,F,W	ICP:A
Selenium	A,F,W	ICP:A	Silicon	A,F,W	ICP:F
Silver	A,F,W	ICP:A	Sodium	A,F,W	ICP:F
Strontium	A,F,W	ICP:A	Tellurium	A,F,W	ICP:A
Thallium	A,F,W	ICP:A	Thorium	A,F,W	ICP:A
Tin	A,F,W	ICP:A	Titanium	A,F,W	ICP:A
Tungsten	A,F,W	ICP:A	Vanadium	A,F,W	ICP:A
Yttrium	A,F,W	ICP:A	Zinc	A,F,W	ICP:A
Zirconium	A,F,W	ICP:A	Chloride	W	IC:W
Cyanide	W	IC:W	Fluoride	W	IC:W
Nitrate	W	IC:W	Nitrite	W	IC:W
Phosphate	W	IC:W	Sulfate	W	IC:W
Ammonia	W	ISE:W	Mercury	A	CVAA:A

Table 4-1. Sample Preparation and Analytical Methods Used on B-201 Samples. (2 pages)

Analyte	Sample Prep.	Preferred Method	Analyte	Sample Prep.	Preferred Method
Curium-243/244	F	Alpha Radchem:F	Gross alpha	F	Alpha Radchem:F
Neptunium-237	F	Alpha Radchem:F	Plutonium-238	F	Alpha Radchem:F
Plutonium-239/240	F	Alpha Radchem:F	Total alpha	F,W	Alpha Radchem:F
Gross beta	F,W	Beta Radchem:F	Strontium-90	F	Beta Radchem:F
Technetium-99	F	Beta Radchem:F	Americium-241	A,F,W	GEA:F
Cerium-144	A,F,W	GEA:F	Cesium-134	A,F,W	GEA:F
Cesium-137	A,F,W	GEA:F	Cobalt-60	A,F,W	GEA:F
Europium-154	A,F,W	GEA:F	Europium-155	A,F,W	GEA:F
Potassium-40	A,F,W	GEA:F	Uranium	F	Laser Fluorimetry:F
Plutonium-239	F	Mass Spectrometry:F	Plutonium-240	F	Mass Spectrometry:F
Plutonium-241	F	Mass Spectrometry:F	Plutonium-242	F	Mass Spectrometry:F
Uranium-234	F	Mass Spectrometry:F	Uranium-235	F	Mass Spectrometry:F
Uranium-236	F	Mass Spectrometry:F	Uranium-238	F	Mass Spectrometry:F
Tritium	W	Liq Scintillation:W	Carbon-14		Liq Scintillation:W
Nickel-59	A	Liq Scintillation:A	Nickel-63	A	Beta Radchem:F
TOC	D,W	Persulfate Oxidation:D	Hex. Chromium	W	Calorimetric:W
Total carbon	D,W	Persulfate Oxidation:W	TIC	D,W	Persulfate Oxidation:W
SVOA		GC/Mass Spectrometry	VOA		GC/Mass Spectrometry

A: acid digestion; CVAA: cold vapor atomic absorption; D: direct analysis; F: KOH/Ni fusion; GC: gas chromatography; ISE: ion-specific electrode; SVOA: semi-volatile organics analysis; VOA: volatile organics analysis; W: water digestion.

Caustic fusion, acid digestion, and water leach preparations of all core composites were completed in the SAL. Tests requiring little or no sample preparation — such as weight percent solids, direct total carbon, direct total inorganic carbon (TIC), direct total organic carbon (TOC), carbon-14, and pH — were conducted in-cell. Due to the low level of radioactivity, aliquots were provided directly to the 325-A Laboratory for mercury, toxicity characteristic leach procedure (TCLP), semivolatile organic analysis, and extractable organic halides analysis.

The SAL made deliberate minor deviations to sample preparation procedures for one or more of the following reasons:

- Insufficient sample was available to conduct the analyses per the specified procedure, and still maintain the level of quality control requested.
- Sample weights and/or final volumes were reduced to facilitate waste minimization.



- Sample weights and/or final volumes were altered to increase the concentration of certain analytes of interest. This was done to meet the concentration ranges needed to perform the analyses, as specified in the procedures.

These deviations are not expected to have a substantive impact on the analytical results or on any conclusions derived from them.

## 5.0 ANALYTICAL RESULTS AND WASTE INVENTORY

A total of 7,598 analytical measurements were made on tank B-201, and Table 5-1 contains a summary of the analytical result counts. As shown, the most complete segment-level analyses were performed on physical properties. The majority of the segment-level chemical analyses were homogenization tests. The only exception is for segment 1 of core 26, which was analyzed for volatile organics. Nearly 33% of all analytical results in the B-201 dataset are quality assurance (QA) data (i.e., matrix spikes, method blanks, etc.). If the homogenization test data is included as QA data, this percentage goes up to 59% (i.e., more than one-half of the analytical results in the B-201 dataset were taken for QA reasons).

Table 5-1. Summary of B-201 Analytical Result Counts.

		Segment								Composite
		1	2	3	4	5	6	7	8	
Physical Properties	Core 26	8	43	7	5	43	5	5	43	8
	Core 27	27	27	15	27	27	23	19	19	0
Chemical Analyses	Core 26	74	0	283	0	0	0	274	0	1,682
	Core 27	0	0	404	0	0	400	0	0	1,641
QA Data		108	0	231	0	0	100	134	0	1,907
Totals		217	70	940	32	70	528	432	62	5,238
		Grand Total (Segment total + Composite total) = 7,598								

The core composite data was used primarily to determine mean concentrations and their associated uncertainties, for the inventory of tank B-201. The segment-level data were used, however, for the analysis of physical properties. A summary of the results from the statistical analysis are given in this section. The complete results are contained in Appendixes B and C.

### 5.1 CHEMICAL ANALYSES AND RADIOLOGICAL DETERMINATIONS

Due to the sampling structure in the B-201 composite data, the following random effects model was fit for each constituent:

$$Y_{ijk} = \mu + C_i + S_{ij} + E_{ijk} \quad (1)$$

where:

$Y_{ijk}$  = The measured value of concentration of a constituent in composite  $j$  of core  $i$

$\mu$  = The mean concentration of the constituent

$C_i$  = The deviation of core  $i$  from the mean (i.e., horizontal variability)

$S_{ij}$  = The deviation of composite  $j$  within core  $i$  from the mean

$E_{ijk}$  = Represents sampling and analytical deviations.

As can be seen, each term in the model describes the contribution of each step in the sampling and measurement process to the observed analytical value (e.g., its calculated mean and the components of variability). For each constituent, this model can be used to obtain a mean concentration estimate, along with its associated uncertainty. This model can also be used to obtain estimates of horizontal variability  $C_i$ , sampling variability  $S_{ij}$ , and analytical variability  $E_{ijk}$  for each constituent.

Table 5-2 lists the tank inventories and concentrations calculated from this analysis of variance (ANOVA) model. Some of the constituents shown in this table were analyzed by more than one method, but only the results from the preferred analytical method are presented. The complete set of constituent results is contained in Appendix B. The historical estimates listed in Table 5-2 are extracted from Table 6-4. The total inventories are calculated using an assumed density of 1.25 g/ml and a total volume of 109,777 liters (29,000 gallons).

Table 5-2. Summary of the Composite Level Results for Anions, Metals, Organics, and Radionuclides. (6 pages)

Analyte	Analytical Method: Sample Preparation	Mean Concentration			Total Inventory
		Composite	RSD	LANL	
Anions					
		(µg/g)		(µg/g)	(kg)
Chloride	IC:W	1.65e+03	7	0.00e+00	2.26e+02
Cyanide	IC:W	3.49e+00	28	NA	4.79e-01
Fluoride	IC:W	5.83e+03	2	8.42e+03	8.00e+02
Nitrate	IC:W	4.93e+04	1	7.13e+04	6.77e+03
Nitrite	IC:W	8.81e+02	13	0.00e+00	1.21e+02
Phosphate	IC:W	1.21e+03	15	1.70e+04	1.66e+02
Phosphate	ICP:F	1.67e+04	NA	NA	2.30e+03
Sulfate	IC:W	3.48e+02	44	0.00e+00	4.78e+01

Table 5-2. Summary of the Composite Level Results for Anions, Metals, Organics, and Radionuclides. (6 pages)

Analyte	Analytical Method: Sample Preparation	Mean Concentration			Total Inventory
		Composite	RSD	LANL	
Cations					
		(µg/g)		(µg/g)	(kg)
Aluminum	ICP:A	3.44e+03	74	NA	4.72e+02
Ammonia	ISE:W	1.04e+01	46	NA	1.43e+00
Antimony	ICP:A	<3.71e+01	NA	NA	<5.09e+00
Arsenic	ICP:A	5.95e+01	NA	NA	8.16e+00
Barium	ICP:A	8.64e+01	38	NA	1.19e+01
Beryllium	ICP:A	<3.71e+00	NA	NA	<5.09e-01
Bismuth	ICP:F	9.45e+04	3	2.96e+04	1.30e+04
Boron	ICP:A	7.05e+01	35	NA	9.67e+00
Cadmium	ICP:A	4.81e+00	6	NA	6.60e-01
Calcium	ICP:A	1.22e+04	58	0.00e+00	1.67e+03
Cerium	ICP:A	6.96e+01	11	NA	9.55e+00
Chromium	ICP:A	3.34e+03	4	1.07e+03	4.58e+02
Cobalt	ICP:A	9.60e+00	4	NA	1.32e+00
Copper	ICP:A	4.82e+01	67	NA	6.61e+00
Dysprosium	ICP:A	<2.94e+01	31	NA	<4.03e+00
Europium	ICP:A	<7.43e+00	NA	NA	<1.02e+00
Gadolinium	ICP:A	1.69e+02	15	NA	2.32e+01
Hexavalent Chromium	Calorimetric:W	7.47e+02	6	NA	1.03e+02
Iron	ICP:F	1.34e+04	20	NA	1.84e+03
Lanthanum	ICP:A	1.51e+04	10	NA	2.07e+03
Lead	ICP:A	1.36e+03	9	NA	1.87e+02
Lithium	ICP:A	<1.49e+01	NA	NA	<2.04e+00
Magnesium	ICP:A	1.51e+03	58	NA	2.07e+02
Manganese	ICP:A	1.92e+04	29	5.77e+03	2.63e+03
Mercury	CVAA:A	5.99e-01	46	NA	8.22e-02
Molybdenum	ICP:A	1.91e+01	4	NA	2.62e+00
Neodymium	ICP:A	<2.23e+01	NA	NA	<3.06e+00
Nickel	ICP:A	4.79e+02	3	NA	6.57e+01
Palladium	ICP:A	<1.11e+02	NA	NA	<1.52e+01
Phosphorus	ICP:F	5.45e+03	14	NA	7.48e+02
Potassium	ICP:A	5.81e+03	13	9.01e+03	7.97e+02
Rhodium	ICP:A	<7.43e+01	NA	NA	<1.02e+01
Ruthenium	ICP:A	<3.71e+01	NA	NA	<5.09e+00

Table 5-2. Summary of the Composite Level Results for Anions, Metals, Organics, and Radionuclides. (6 pages)

Analyte	Analytical Method: Sample Preparation	Mean Concentration			Total Inventory
		Composite	RSD	LANL	
Selenium	ICP:A	6.68e+01	9	NA	9.17e+00
Silicon	ICP:F	2.02e+04	63	NA	2.77e+03
Silver	ICP:A	1.23e+01	20	NA	1.69e+00
Sodium	ICP:F	3.82e+04	2	3.90e+04	5.24e+03
Strontium	ICP:A	9.23e+02	5	NA	1.27e+02
Tellurium	ICP:A	<7.43e+01	NA	NA	<1.02e+01
Thallium	ICP:A	<3.71e+02	NA	NA	<5.09e+01
Tin	ICP:A	5.96e+02	NA	NA	8.18e+01
Titanium	ICP:A	2.85e+02	75	NA	3.91e+01
Tungsten	ICP:A	5.96e+01	NA	NA	8.18e+00
Uranium	Laser Fluorimetry:F	1.56e+02	100	0.00e+00	2.14e+01
Vanadium	ICP:A	1.59e+01	38	NA	2.18e+00
Yttrium	ICP:A	8.19e+00	18	NA	1.12e+00
Zinc	ICP:A	2.17e+02	6	NA	2.98e+01
Zirconium	ICP:A	1.07e+01	10	NA	1.47e+00
Organics					
		(µg/g)		(µg/g)	(kg)
1,2,4-Trichlorobenzene	SVOA	<4.80e+01	NA	NA	<6.59e+00
1,2-Dichlorobenzene	SVOA	<4.80e+01	NA	NA	<6.59e+00
1,3-Dichlorobenzene	SVOA	<4.80e+01	NA	NA	<6.59e+00
1,4-Dichlorobenzene	SVOA	<4.80e+01	NA	NA	<6.59e+00
2,4,5-Trichlorophenol	SVOA	<2.40e+02	NA	NA	<3.29e+01
2,4,6-Trichlorophenol	SVOA	<4.80e+01	NA	NA	<6.59e+00
2,4-Dichlorophenol	SVOA	<4.80e+01	NA	NA	<6.59e+00
2,4-Dimethylphenol	SVOA	<4.80e+01	NA	NA	<6.59e+00
2,4-Dinitrophenol	SVOA	<2.40e+02	NA	NA	<3.29e+01
2,4-Dinitrotoluene	SVOA	<4.80e+01	NA	NA	<6.59e+00
2,6-Dinitrotoluene	SVOA	<4.80e+01	NA	NA	<6.59e+00
2-Chloronaphthalene	SVOA	<4.80e+01	NA	NA	<6.59e+00
2-Chlorophenol	SVOA	<4.80e+01	NA	NA	<6.59e+00
2-Methylnaphthalene	SVOA	<4.80e+01	NA	NA	<6.59e+00
2-Methylphenol	SVOA	<4.80e+01	NA	NA	<6.59e+00
2-Nitroaniline	SVOA	<2.40e+02	NA	NA	<3.29e+01
2-Nitrophenol	SVOA	<4.80e+01	NA	NA	<6.59e+00
3,3'-Dichlorobenzidine	SVOA	<9.69e+01	NA	NA	<1.33e+01
3-Nitroaniline	SVOA	<2.40e+02	NA	NA	<3.29e+01
4,6-Dinitro-o-cresol	SVOA	<2.40e+02	NA	NA	<3.29e+01

Table 5-2. Summary of the Composite Level Results for Anions, Metals, Organics, and Radionuclides. (6 pages)

Analyte	Analytical Method: Sample Preparation	Mean Concentration			Total Inventory
		Composite	RSD	LANL	
4-Bromophenylphenyl ether	SVOA	<4.80e+01	NA	NA	<6.59e+00
4-Chloro-3-methylphenol	SVOA	<4.80e+01	NA	NA	<6.59e+00
4-Chloroaniline	SVOA	<4.80e+01	NA	NA	<6.59e+00
4-Methylphenol	SVOA	<4.80e+01	NA	NA	<6.59e+00
4-Nitroaniline	SVOA	<2.40e+02	NA	NA	<3.29e+01
4-Nitrophenol	SVOA	<2.40e+02	NA	NA	<3.29e+01
Acenaphthene	SVOA	<4.80e+01	NA	NA	<6.59e+00
Acenaphthylene	SVOA	<4.80e+01	NA	NA	<6.59e+00
Anthracene	SVOA	<4.80e+01	NA	NA	<6.59e+00
Benzo(a)anthracene	SVOA	<4.80e+01	NA	NA	<6.59e+00
Benzo(a)pyrene	SVOA	<4.80e+01	NA	NA	<6.59e+00
Benzo(b)fluoranthene	SVOA	<4.80e+01	NA	NA	<6.59e+00
Benzo(ghi)perylene	SVOA	<4.80e+01	NA	NA	<6.59e+00
Benzo(k)fluoranthene	SVOA	<4.80e+01	NA	NA	<6.59e+00
Benzoic acid	SVOA	<2.40e+02	NA	NA	<3.29e+01
Benzyl alcohol	SVOA	<4.80e+01	NA	NA	<6.59e+00
Bis(2-chloroethyl) ether	SVOA	<4.80e+01	NA	NA	<6.59e+00
Bis(2-chloroisopropyl )	SVOA	<4.80e+01	NA	NA	<6.59e+00
Butylbenzylphthalate	SVOA	<4.80e+01	NA	NA	<6.59e+00
Chrysene	SVOA	<4.80e+01	NA	NA	<6.59e+00
Di-n-butylphthalate	SVOA	<4.80e+01	NA	NA	<6.59e+00
Di-n-octylphthalate	SVOA	<4.80e+01	NA	NA	<6.59e+00
Dibenz[a,h]anthracene	SVOA	<4.80e+01	NA	NA	<6.59e+00
Dibenzofuran	SVOA	<4.80e+01	NA	NA	<6.59e+00
Diethylphthalate	SVOA	<4.80e+01	NA	NA	<6.59e+00
Dimethyl phthalate	SVOA	<4.80e+01	NA	NA	<6.59e+00
Dodecane	SVOA	2.85e+02	8	NA	3.91e+01
Fluoranthene	SVOA	<4.80e+01	NA	NA	<6.59e+00
Fluorene	SVOA	<4.80e+01	NA	NA	<6.59e+00
Hexachlorobenzene	SVOA	<4.80e+01	NA	NA	<6.59e+00
Hexachlorobutadiene	SVOA	<4.80e+01	NA	NA	<6.59e+00
Hexachloroethane	SVOA	<4.80e+01	NA	NA	<6.59e+00
Indeno(1,2,3-cd)pyrene	SVOA	<4.80e+01	NA	NA	<6.59e+00
Isophorone	SVOA	<4.80e+01	NA	NA	<6.59e+00
N-Nitrosodiphenylamine	SVOA	<4.80e+01	NA	NA	<6.59e+00
Naphthalene	SVOA	<4.80e+01	NA	NA	<6.59e+00
Nitrobenzene	SVOA	<4.80e+01	NA	NA	<6.59e+00

Table 5-2. Summary of the Composite Level Results for Anions, Metals, Organics, and Radionuclides. (6 pages)

Analyte	Analytical Method: Sample Preparation	Mean Concentration			Total Inventory
		Composite	RSD	LANL	
Pentachlorophenol	SVOA	<2.40e+02	NA	NA	<3.29e+01
Pentadecane	SVOA	4.10e+01	37	NA	5.63e+00
Phenanthrene	SVOA	<4.80e+01	NA	NA	<6.59e+00
Phenol	SVOA	<4.80e+01	NA	NA	<6.59e+00
Pyrene	SVOA	<4.80e+01	NA	NA	<6.59e+00
Tetradecane	SVOA	1.03e+03	28	NA	1.41e+02
Total carbon	Persulfate Oxidation:W	2.55e+03	12	NA	3.50e+02
Total inorganic carbon	Persulfate Oxidation:W	2.09e+03	16	NA	2.87e+02
Total organic carbon	Persulfate Oxidation:W	5.18e+02	10	4.58e+03	7.11e+01
Tridecane	SVOA	9.29e+02	7	NA	1.27e+02
Physical Properties					
		(%)		(%)	
Weight percent solids	Percent Solid	3.93e+01	3	NA	NA
Radionuclides					
		( $\mu\text{Ci/g}$ )		( $\mu\text{Ci/g}$ )	(Ci)
Americium-241	GEA:F	3.10e-02	4	NA	4.25e+00
Carbon-14	Liq Scintillation:W	3.16e-04	NA	NA	4.34e-02
Cesium-134	GEA:F	2.38e-03	NA	NA	3.27e-01
Cesium-137	GEA:F	8.00e-01	27	NA	1.10e+02
Cobalt-60	GEA:F	1.96e-03	75	NA	2.69e-01
Curium-243/244	Alpha Radchem:F	1.64e-03	21	NA	2.25e-01
Europium-154	GEA:F	4.38e-03	51	NA	6.01e-01
Europium-155	GEA:F	3.28e-03	NA	NA	4.50e-01
Gross alpha	Alpha Radchem:F	1.31e+00	18	NA	1.80e+02
Gross beta	Beta Radchem:F	4.41e+00	28	NA	6.05e+02
Neptunium-237	Alpha Radchem:F	<1.24e-04	NA	NA	<1.70e-02
Nickel-59	Beta Radchem:A	6.86e-06	22	NA	9.41e-04
Nickel-63	Liq Scintillation:A	1.88e-04	25	NA	2.58e-02
Plutonium-238	Alpha Radchem:F	3.48e-03	98	NA	4.78e-01
Plutonium-239/240	Alpha Radchem:F	1.13e+00	30	NA	1.55e+02
Strontium-90	Beta Radchem:F	2.09e+00	51	0.00e+03	2.87e+02
Technetium-99	Beta Radchem:F	<1.94e-03	NA	NA	<2.66e-01
Total alpha*	Alpha Radchem:F	1.14e+00	NA	NA	1.56e+02
Tritium	Liq Scintillation:W	2.05e-02	78	NA	2.81e+00

Table 5-2. Summary of the Composite Level Results for Anions, Metals, Organics, and Radionuclides. (6 pages)

Analyte	Analytical Method: Sample Preparation	Mean Concentration			Total Inventory
		Composite	RSD	LANL	
		(%)		(%)	
Uranium-234	Mass Spectrometry:F	5.40e-03	6	NA	NA
Uranium-235	Mass Spectrometry:F	6.91e-01	0	NA	NA
Uranium-236	Mass Spectrometry:F	5.20e-03	6	NA	NA
Uranium-238	Mass Spectrometry:F	9.93e+01	0	NA	NA
Plutonium-239	Mass Spectrometry:F	9.84e+01	0	NA	NA
Plutonium-240	Mass Spectrometry:F	1.55e+00	1	NA	NA
Plutonium-241	Mass Spectrometry:F	1.30e-02	16	NA	NA
Plutonium-242	Mass Spectrometry:F	3.84e-03	43	NA	NA

\*Total alpha emitted from <sup>238</sup>Pu, <sup>239</sup>Pu, <sup>240</sup>Pu, <sup>241</sup>Pu; NA: Not Available or Not Applicable.

Table 5-2 shows each constituent's mean concentration and relative standard deviation (RSD) on the mean. The RSD is the square root of the variance estimate divided by the mean of the constituent, which indicates how large the variance estimate is relative to the mean. If a sample result was below the detection limit, the detection limit was used in the fit of the random effects model. If more than 75% of the sample results for a given constituent were below the detection limit, the random effects model was not fit. In that case, a mean was taken and no RSD information was reported.

The plutonium analyses done for core 26 and core 27 were not identical. In the case of core 26, the alpha contributors were chemically separated, and an alpha energy analysis was done. This assay provided the concentrations of Plutonium-238, Plutonium-239/240, and Americium-241. In the case of core 27, a total alpha measurement was taken and the contributors from the various alpha emitters resolved. The sample was then chemically prepared and assayed with a mass spectrometer to determine the isotopic content of the plutonium in the sample. In order to provide a representative estimate of the plutonium inventory for tank B-201, the information in core 27 about plutonium content and isotopic distribution was used to determine the corresponding values found in the core 26 measurements and included in the ANOVA analyses.

The boxplots in Figure 5-1 illustrate the magnitude of horizontal, sampling, and analytical variance components relative to each other. The "box" for a given boxplot represents the range of the middle 50% of the RSDs. The vertical line in each box is the median RSD value and the lines (whiskers) coming out the ends of the boxes represent the entire range of the RSDs. For all subgroupings of constituents (anions, cations or metals, organics, radionuclides), the horizontal spatial variability is generally the largest source of variability. The long whisker on the horizontal variability boxplot for the radionuclides is due to the total uranium measurement.



Figure 5-1. RSD Distributions for Variance Components Calculated from the Composite-Level Data.




Table 5-3 contains a list of several of the constituents grouped according to the core in which they were found in highest concentration. Constituents were grouped with one core or the other only if the differences between core results were greater than the uncertainty due to sampling and analytical error. For the three constituents measured in highest concentration in B-201 core samples (bismuth, nitrate, and sodium), there were no statistical differences between the cores. However, for a number of the other constituents in large concentration in the core samples (calcium, lanthanum, potassium, iron, phosphorus, silicon), the concentrations found in core 26 were significantly greater than those found in core 27. Constituents were excluded from this analysis if 75% or more of the sample and duplicate results were below the detection limit (i.e., no ANOVA was run).

Table 5-3. Analytes Grouped According to Concentration Differences Between Cores.

Analytes with Higher Concentrations for Core 26		
Hexavalent Chromium	Strontium-90	Cobalt-60
Europium-154	Aluminum	Barium
Calcium*	Chromium	Copper
Dysprosium	Lanthanum*	Magnesium
Potassium*	Silver	Titanium
Vanadium	Iron*	Phosphorus*
Silicon*	Chloride	Cyanide
Nitrite	Sulfate	Tritium
Plutonium-242	Nickel-59	Ammonia
Pentadecane	Tetradecane	Total carbon
Total inorganic carbon		
Analytes with no Statistical Differences Between Cores		
Gross Beta	Americium-241	Cadmium
Cerium	Cobalt	Gadolinium
Bismuth*	Manganese*	Molybdenum
Nickel	Selenium	Strontium
Yttrium	Zinc	Sodium
Fluoride	Nitrate*	Zirconium
Plutonium-239	Plutonium-240	Plutonium-241
Uranium-234	Uranium-236	Nickel-63
Dodecane	Tridecane	Total organic carbon
Analytes with Higher Concentrations for Core 27		
Gross Alpha	Cesium-137	Boron
Lead	Phosphate	Uranium
Uranium-235		

\*Analyte present in concentrations > 5000 µg/g.

As the analytical results from B-201 core samples were reviewed, several anomalous results were noted. In many cases, these were excluded from the reported statistical results; while in other cases, they were only identified as "outliers" but used in the analyses.

Table 5-4 shows the sample results that were excluded from the random effects model fits. These results were excluded because of their large disagreements with the other results for a particular constituent. The core 26 and core 27 Laboratory Reports (Shaver 1993) were consulted in order to assign reasons for anomalous results.

Table 5-4. Composite Values Omitted from Analyses as Suspect.

Analyte	Method	Core	Composite	Aliquot	Value	Below DL	Units
Bismuth	ICP:W	26	1	1	49.61	yes	$\mu\text{g/g}$
Iron	ICP:W	26	1	1	16.8	no	$\mu\text{g/g}$
Nickel	ICP:W	26	1	1	14.883	yes	$\mu\text{g/g}$
Strontium	ICP:W	26	1	1	2,481	yes	$\mu\text{g/g}$
Arsenic	ICP:F	26	1	2	636.7	no	$\mu\text{g/g}$
Copper	ICP:F	26	1	2	358.5	no	$\mu\text{g/g}$
Iron	ICP:F	27	1	2	12409	no	$\mu\text{g/g}$
Lead	ICP:F	27	1	2	1959	no	$\mu\text{g/g}$
Chloride	IC:W	26	2	2	2000	no	$\mu\text{g/g}$
Fluoride	IC:W	26	2	2	7200	no	$\mu\text{g/g}$
Nitrate	IC:W	26	2	2	59000	no	$\mu\text{g/g}$
Phosphate	IC:W	26	2	2	1300	no	$\mu\text{g/g}$
Cobalt-60	GEA:F	26	1	2	0.00859	no	$\mu\text{Ci/g}$
Tritium	Liq Scintillation	26	2	1	0.113	no	$\mu\text{Ci/g}$
Uranium-235	Mass Spectrometry	26	2	2	0.5825	no	%

The results reported in Table 5-4 for bismuth, iron, nickel, and strontium (ICP:W) are all from the same aliquot. These four constituents are not expected to be water soluble, and all of the analytical results are close to the detection limits. Because of these conditions, the variability for these analytes is expected to be large. Hence, these results were removed from the random effects model fits.

The arsenic and copper results (ICP:F) reported in Table 5-4 are from the same aliquot. For both constituents, the results from this aliquot are much larger than the other results from the same core (core 26), and these two results were removed from the model fits.

The lead and iron results (ICP:F) reported in Table 5-4 are from the same aliquot. The RPDs for the primary and duplicate results on three of the composites were small for three pairs (e.g., 1%). The RPD for the other composite (core 26, composite 1) was somewhat larger (19.1% for lead and 6.6% for iron). The primary result is closer to the range of results from the other three composites. For this reason, the duplicate results (core 26, composite 1) for iron and lead were dropped from the model fits.


The results reported in the table for chloride, fluoride, nitrate, and phosphate (IC:W) are also from the same aliquot (core 26, composite 2, aliquot 2). This aliquot result is unusually higher than the other three results from the same core, which are in agreement with one another. The core 26 data report (Shaver 1993) notes that the RPDs are high for

the duplicate pairs from core 26. That report attributes the large RPD values to poor sample homogenization. For this reason, these results were removed from the random effects model fits.

The cobalt-60, tritium, and uranium-235 results reported in Table 5-4 were outside the range of other results for the given constituent. The core 26 data report (Shaver 1993) indicates that the process blanks showed significant tritium contamination from previous tritium work. These three results were not used in the random effects model fits.

Figure 5-2 shows a residuals pattern that was noted for several constituents analyzed by the ICP:A method. This plot shows the predicted values from the random effects model fit plotted against the residuals from the fit. If the random effects model (Equation 1) were valid, this plot would show a horizontal band of residuals varying evenly about zero. The four residuals that have the largest absolute values are from core 26, composite 1. The core 26 data report (Shaver 1993) notes that these large differences between the sample and duplicate results are due to poor sample homogenization or poor subsampling. These anomalous results were not removed from the statistical analysis, however, because of the limited amount of data available.

Figure 5-2. Residuals Plot for ICP Acid Digestion Aluminum Analysis.  
Predicted VS Residuals for Aluminum



Two different types of ICP fusion analyses were performed on B-201 core samples. The first used sodium peroxide with a zirconium crucible. It was noted that this method created an unknown white precipitate during sample analyses. The second used potassium

hydroxide with a nickel crucible. The sample results from the sodium peroxide method were excluded from any results presented in this report, except for nickel and potassium. Nickel and potassium results are reported, since the ICP results with potassium hydroxide fusion are invalid for these two constituents.

## 5.2 PHYSICAL MEASUREMENTS

The physical measurements made on the waste are summarized in Table 5-5, which shows the averages of the available measurements for the as-received sample, 1:1 and 3:1 water to sample dilutions. The measurements were made on several segments of core 26. Since the waste materials in cores 26 and 27 are visually different, lateral heterogeneity is suspected, and the summaries in the table may provide a biased description of the waste's physical properties. A preferable set of measurements would include complete segment-level measurements on both cores, so that both horizontal and vertical variability could be adequately assessed.

Table 5-5. Summary of Core 26 Physical Measurements.

Analyte	Units	Segments		
		2	5	8
Segment - As Received				
Weight % settled solids	%	100	100	100
Density	g/mL	1.65	1.51	1.34
Volume % centrifuged solids	%	98	98	88
Weight % centrifuged solids	%	98	98	90
Centrifuged Supernate Density	g/mL	1.19	1.19	1.05
Centrifuged Solids Density	g/mL	1.66	1.52	1.37
Shear Strength	dynes/cm <sup>2</sup>	14100	13100	12200
Segment - 1:1 Water to Sample Dilution				
Volume % Settled Solids	%	83	81	92
Density	g/mL	1.33	1.17	1.13
Volume % centrifuged solids	%	58	43	42
Weight % centrifuged solids	%	69	52	49
Centrifuged Supernate Density	g/mL	1.01	1.00	0.99
Centrifuged Solids Density	g/mL	1.59	1.40	1.33
Segment - 3:1 Water to Sample Dilution				
Volume % Settled Solids	%	42	37	57
Density	g/mL	1.10	1.05	1.05
Volume % centrifuged solids	%	24	16	21
Weight % centrifuged solids	%	32	21	25
Centrifuged Supernate Density	g/mL	0.99	1.00	0.99
Centrifuged Solids Density	g/mL	1.48	1.36	1.24

The values shown for the as-received segment samples are more appropriate descriptions of the individual segments, rather than representative of the tank as a whole. For example, the segment level densities are much higher than the calculated bulk density of 1.25 g/mL. The values for the water to sample dilutions represent the potential matrix characteristics if the waste is sluiced.

The RSD reported in Appendix C for these analysis represents spatial RSD, not the uncertainty in the reported measurement. Since measurements were typically taken on several vertical segments within a single core, the spatial variability represented in the RSD is vertical variability.

### 5.2.1 Physical and Rheological Properties

The important physical measurements recorded include density, temperature (in situ), and three different measurements of weight percent solids.

The estimated mean for weight percent solids was 39.3%. This result was based on the analysis of core 26 composite samples only. This value was also used to calculate the estimated percent water (60.7%) in the mass and charge balance discussed in Section 7.0. Table 5-6 shows the weight percent solids on a segment level basis for both core 26 and 27. A substantial lateral heterogeneity is exhibited, with core 26 having a much higher water content.

Table 5-6. Weight Percent Solids.

Segment	Core 26	Core 27
1	51.8	33.5
2	53.6	28.4
3	29.5	96.7
4	29.8	42.8
5	31.6	46.9
6	33.5	66.4
7	28.9	82.6
8	28.0	68.3
Composite 1	39.0	No Measurement
Composite 2	39.5	No Measurement

The pH of the water leaches of the core 26 composite materials (100:1 dilution followed by filtration) and of 10:1 water-to-sample slurries of the core composite materials was measured according to PNL-ALO-225. The average pH for the water leaches of the

---

composites was 8.5 and 8.6 for composites 1 and 2, respectively. The calibration check (made after the measurement of the samples) using a pH 7 buffer was out of control. The measured pH for this calibration check was 6.5. The pH of the 10:1 slurries was 11.0 for each of the core composite slurries. All calibrations and checks were in control during and after the analysis of the 10:1 slurry sample.

The pH of the water leaches of the core 27 composite materials (100:1 dilution followed by filtration) was measured in duplicate, according to PNL-ALO-225. The pH for the water leaches of the composites was 8.3 for both composites 1 and 2.

The penetration resistance for core 26 was measured on each of the extruded segments except segment 1, which did not have enough solids to make an accurate measurement. The penetration measurement was made on the unhomogenized segment material prior to any further subsampling. These measurements were made after the sample had been sealed in a bottle for approximately six months. The penetration resistance for all segments was less than 3 psi; therefore, the sludge is cohesive and will be broken into pieces by the mixer pump instead of being eroded. The penetration resistance is calculated by dividing the measured resistance by 16, since the 1-inch shoe was used to measure these minimal resistances.

The penetration resistance for core 27 was measured on each of the extruded segments. This measurement was made on the unhomogenized segment material prior to any further subsampling. These measurements were made after the sample had been sealed in a bottle for approximately one year. The penetration resistance for all segments was greater than 1 psi. The penetration resistance is calculated by dividing the measured resistance by 16, since the 1-inch shoe was used in place of the 1/4-inch shoe. The 1-inch shoe is used to measure small penetration resistances. These low penetration resistances indicate that the sludge is cohesive.

To summarize, the penetrometer readings were all less than 3 psi (the reporting limit), indicating that the waste is not very cohesive. From the rheological measurements, one can draw the conclusion that the waste is not solid and can be pumped. Further rheological analysis regarding the flow behavior of the waste can be found in Appendix E.

### 5.2.2 Energetics

The most notable observation drawn from the thermal analysis is that no exotherms were found. Thermal measurements were made on all eight segments of core 27, so it can be relatively assured that no exothermic layer exists in this waste. Table 5-7 shows the individual results for each segment in core 27.

Table 5-7. Core 27 Differential Scanning Calorimetry Thermal Measurements.

Segment	Transition 1			Transition 2		
	Enthalpy (cal/g)	Onset (°C)	Range (°C)	Enthalpy (cal/g)	Onset (°C)	Range (°C)
1	295	64	34-140	16	143	132-217
2	290	73	34-141	88	158	137-340
3	NO	NO	NO	4	123	106-153
4	272	64	34-125	8	134	125-191
5	251	66	34-139	14	146	135-235
6	210	62	37-183	8	153	147-210
7	135	46	37-146	NO	NO	NO
8	200	51	35-158	NO	NO	NO

NO: Not Observed.

However, the thermal analysis did identify two endotherms in the waste, which together generally absorbed over 800 J/g (200 cal/g). These two endotherms occurred between ambient and 140 °C (284 °F); and between 140 and 223 °C (433 °F). These endotherms are believed to be the result of the loss of free and bound water.

### 5.2.3 Particle Size Analysis

The particle size distribution was measured on unhomogenized material from each of the segments of core 26. The particle size analyzer determines particle sizes in the range of 0.5 to 150  $\mu\text{m}$  by measuring the time required for a rapidly moving laser beam to traverse selected particles maintained in a stirred suspension. A glass sphere reference (Duke 147) was measured prior to running the samples, to ensure proper operation of the instrument.

Results from this analysis show that most of the particles in these samples are less than 6 microns in diameter, based on the number density. The volume density data indicates that there is a small percentage of particles of much larger size, but it appears that only a few of the particles exceed 80 microns in diameter. Individual quantitative segment results for core 26 were not found in the data package, however, distribution profiles were presented.

The particle size distribution for core 27 was measured on unhomogenized material from each of the segments. This analysis was performed according to PNL-ALO-530 Rev 0. Results show that most of the particles in these samples are less than 2 microns in diameter, based on the number density. The median particle diameters based on number and volume densities are  $0.91 \pm 0.06$  and  $22.4 \pm 13.2$  microns, respectively. The volume density data



indicates that there is a small percentage of particles of much larger size, but it appears that only a few of the particles exceed 100 microns in diameter. Table 5-8 provides the individual segment results for core 27, and again, distribution profiles can be found in the data package. No discernible trend is observed in the particle size data as a function of depth.

Table 5-8. Particle Size Distribution for Core 27.

Segment	Particle Size, microns (by number)		Particle Size, microns (by volume)	
	Mean	Median	Mean	Median
1	1.13	0.88	26.37	19.98
2	1.31	0.91	65.55	46.62
3	1.48	0.92	30.47	21.63
4	1.07	0.84	18.02	12.08
5	1.16	0.87	9.42	6.46
6	1.56	1.03	41.79	37.49
7	1.24	0.93	18.65	17.45
8	1.10	0.86	23.24	17.65

### 5.3 HEAT LOAD ANALYSIS

The waste in tank B-201 is not very radioactive and consequently generates very little heat through radioactive decay. The most significant radioactive contributors in the waste are strontium-90, cesium-137, and plutonium; contributing 287, 110, and 109 curies, respectively. Table 5-9 summarizes the power produced by the radionuclides in the waste. As one can see, only about 6 watts of heat are produced, not enough energy to power a normal light bulb.

Table 5-9. Radionuclide Inventory and Projected Heat Load.

	Total Ci	kW/Ci	kW
Americium-241	4.25e+00	3.26e-05	1.39e-04
Cesium-134	3.27e-01	1.02e-05	3.34e-06
Cesium-137	1.10e+02	4.72e-06	5.19e-04
Cobalt-60	2.69e-01	1.54e-05	4.13e-06
Curium-243/244	2.25e-01	3.47e-05	7.81e-06
Plutonium-238	9.47e-01	3.33e-05	3.16e-05
Plutonium-239/240	1.09e+02	3.06e-05	3.33e-03
Strontium-90	2.87e+02	6.67e-06	1.91e-03
Technetium-99	2.66e-01	5.00e-07	1.33e-07
<b>Total</b>			<b>5.95e-03</b>

## **6.0 INTERPRETATION OF ANALYTICAL RESULTS**

This section discusses and interprets the results of the core sample analysis for tank B-201. The first analysis performed was a tank waste profile. This analysis provides information about analyte concentrations as a function of depth. It also provides information about the dominant sources of variability (e.g., spatial or laboratory) in the analytical results. The second analysis is a comparison of the analytical results to the available historical estimates.

### **6.1 TANK WASTE PROFILE**

Segment-level measurements can be used to describe the vertical variability of a tank, and to create a tank profile. However development of such a profile is subject to two important limitations. First, the segments allow no finer resolution than 19 in., because they are homogenized before measurement. Secondly, all core segments have not been processed through the same analytical suite in the chemistry lab. In many tanks, sampling plans call for only composite measurements to be taken. The current tank is an example of this guidance. For tank B-201, the only segment-level measurements taken were for the homogenization test.

In this section, the homogenization test data is used to evaluate spatial variability within the tank and to produce a crude tank profile. Homogenization measurements were taken on approximately 50 constituents. These measurements were generally taken on only two segments of the eight that make up a core. One measurement was taken from the middle of the tank (segment 3) and one from the bottom of the tank (segment 6 or 7), so only an incomplete tank profile can be constructed.

Table 6-1 presents a summary of the segment-level measurements available. As one can see from the table, the most complete measurements appear to be the physical measurements. For many physical properties, all 8 segments within a core were measured. However, the measurements were typically made on only one core.

Table 6-1. Available Segment-Level Measurements.

Core	Segments							
	1	2	3	4	5	6	7	8
<b>Anions</b>								
26	0	0	4	0	0	0	4	0
27	0	0	8	0	0	8	0	0
<b>Metals</b>								
26	0	0	176	0	0	0	176	0
27	0	0	352	0	0	352	0	0
<b>Organics</b>								
26	74	0	74	0	0	0	74	0
27	0	0	0	0	0	0	0	0
<b>Physical</b>								
26	8	43	5	5	43	5	5	43
27	27	27	15	27	27	23	19	19
<b>Radionuclides</b>								
26	0	0	31	0	0	0	20	0
27	0	0	44	0	0	40	0	0

To evaluate this data, a two-way ANOVA model was fit to it. The ANOVA model has the form:

$$Y_{ijk} = \mu + C_i + S_j + CS_{ij} + E_{ijk} \quad (2)$$

where:

$Y_{ijk}$  = The measured value of concentration of a constituent in segment  $j$  of core  $i$

$\mu$  = The mean concentration of the constituent in the tank

$C_i$  = The deviation of core  $i$  from the mean (i.e., horizontal variability)

$S_j$  = The deviation of segment  $j$  from the mean (i.e., vertical variability)

$CS_{ij}$  = Represents general spatial deviations from the mean

$E_{ijk}$  = Represents sampling and analytical deviations.

The ANOVA algorithm produces variance estimates for each of the deviations listed in the model above:

$\sigma_C^2$  = Horizontal variability estimate

$\sigma_S^2$  = Vertical variability estimate

$\sigma_{CS}^2$  = General spatial variability estimate

$\sigma_E^2$  = Residual variability estimate

as well as estimates for all of the model terms. These variance estimates provide the best summaries of tank spatial homogeneity.

For example, if  $\sigma_C$  is dominant, then there are large horizontal variations in the waste. If  $\sigma_S$  is dominant, then the waste has very definite layers. Finally, if  $\sigma_{CS}$  is dominant, then the waste is spatially inhomogeneous, but the inhomogeneities are not associated with the vertical or horizontal direction in the tank.

For this particular data set, the segment term was collapsed into three levels: top (segment 1), middle (segments 2 through 5), and bottom (segments 6 through 8). Appendix C provides a complete description of the ANOVA results. The first part of Appendix C lists the variance estimates for all the constituents available and the second part provides tank profile plots.

Table 6-2 summarizes the spatial variabilities found in the tank. Vertical variability is the largest, with general spatial variability  $\sigma_{CS}$  a close second. Horizontal variability is the smallest observed spatial variability, although from a qualitative standpoint it appears significant as well (e.g., the visually discernable difference observed between cores 26 and 27).

Table 6-2. Summary of RSD Values.

	Mean RSD (%)			
	$\sigma_C$	$\sigma_S$	$\sigma_{CS}$	$\sigma_E$
Anions	0	13	13	4
Metals	14	44	33	14
Organics		38		27
Physical	10	17	11	28
Radionuclides	18	31	16	31

One can also classify the individual constituents by their variabilities. These results are presented in Table 6-3. From this perspective, vertical variability is largest for 29 constituents, and horizontal for only 3; a further indication that layering is the dominant type of spatial variability in this tank.

Table 6-3. Analytes Classified by Dominant RSD.

Core ( $\sigma_s$ )	Segment ( $\sigma_s$ )	
Temperature	Phosphorus*	Aluminum
Europium-154	Bismuth	Calcium
Europium-155	Chromium	Copper
	Iron	Lanthanum
	Lead	Magnesium
	Nickel	Potassium
	Sodium	Strontium
	Zinc	Hexamethyldisiloxane
	Methoxytrimethylsilane	Toluene
	Trimethylsilanol	Centrifuged solids
	Density	Critical flow rate-2inch
	Critical flow rate-3inch	Critical velocity-2inch
	Critical velocity-3inch	Shear strength
	Yield point	Americium-241
	Cesium-137	
Core x Segment ( $\sigma_{CS}$ )	Residuals ( $\sigma_R$ )	
Phosphorus*	Manganese	Molybdenum
Barium	Silver	Uranium
Boron	Hexamethyldisiloxane	Centrifuged supernate density
Silicon	Density	Flow behavior index
Titanium	Particle size number density mean	Particle size volume density mean
Zirconium	Reynolds number-2inch	Reynolds number-3inch
	Settled solids	Volume % centrifuged solids
	Weight loss %	Weight % centrifuged solids
	Weight % solids	Cesium-134
	Cobalt-60	

\*Phosphorus  $\sigma_s$  and  $\sigma_{CS}$  are equal.

## 6.2 WASTE SUMMARY AND CONDITIONS

Table 6-4 presents a comparison of historical data to current sampling results. The second and third columns in this table present the best predictions by LANL (Table 2-1) and the 1978 sampling campaign (Table 3-2). The second column presents the most authoritative set of historical estimates and this column should be compared to the fourth column (composite sampling results) to determine how good the LANL historical estimates are.

Table 6-4. Comparison of Mean Tank Estimates (Historical versus Sampling Results).

Constituent	Historical		Composite Data		RPE*	
	LANL	78 Sampling	Est.	%-RSD	LANL	78
	(μg/g)					
Aluminum	0	10000	3440	74	100	191
Bismuth	29600	38000	94100	3	-68.6	-59.6
Calcium	0	NA	12200	58	-100	NA
Carbonate	0	33000	NA	NA	NA	NA
Chloride	0	100	1650	7	-100	-93.9
Chromium	1070	500	3340	4	-68	-85
Fluoride	5130	NA	5830	2	-12	NA
Hydroxide	8420	6000	NA	NA	NA	NA
Iron	0	18000	13400	20	-100	34
Lanthanum	0	13000	15100	10	-100	-13.9
Manganese	5770	30	19200	29	-69.9	-99.8
Mercury	0	500	0.599	46	-100	83400
Nickel	0	1000	479	3	-100	109
Nitrate	71300	33000	49300	1	44.6	-33.1
Nitrite	0	40	881	13	-100	-95.5
Oxalate	16800	NA	NA	NA	NA	NA
Phosphate	17000	11000	1210	15	1310	809
Potassium	9010	3000	5810	13	55.1	-48.4
Silicate	0	3000	29700	75	-100	-89.9
Sodium	39000	28000	38200	2	2.1	-26.7
Sulfate	0	600	348	44	-100	72.4
TOC	4580	NA	518	10	784	NA
Uranium	0	10.5	156	100	-100	-93.3
	(μCi/g)					
Americium-241	0	0.005	0.031	4	-100	-83.9
Cesium-137	0	0.059	0.800	27	-100	-92.6
Europium-155	0	0.028	0.00328	NA	-100	754
Plutonium	0.964	856**	1.14	NA	-15.4	74988
Strontium-90	0	2.7	2.09	51	-100	29.2
Weight % solids	19.9	27.8	39.3	3	-49.4	-29.3

\*RPE = Relative Percent Error: (Measured - true)/true.

\*\*Measurement not considered credible; likely a transcription error.

The fourth column contains estimates obtained from the ANOVA fits described in Section 5.0, together with the RSD of the ANOVA estimates. A complete tabulation of our best estimate for each constituent is shown in Table 5-2. The two final columns in Table 6-4 present the relative percent errors for the LANL and 1978 predictions.

Of the 29 constituents listed in Table 6-4, 5 show good agreement, with less than a  $\pm 50\%$  difference between LANL historical results and measured values. Good agreement was obtained for fluoride, nitrate, sodium, plutonium, and weight percent solids.

However, except for those constituents that were missed altogether, the LANL estimates are within a factor of 10. As a general rule of thumb, one can conclude that when a LANL estimate is present, it is good to within a factor of 10.

It is interesting to note that there are also some significant differences between the results taken in 1978 and the present results. For example, mercury is 3 orders of magnitude larger in the 1978 results than presently. Also, there are very large differences in the radionuclide estimates.


The type of sample that was taken and analyzed is not known; given the poor agreement between the 1978 results and the present results, it is plausible that the 1978 sample might have been of the supernate only.

Table 6-5 provides a means of determining internal consistency for the principal radionuclides. The gross alpha and gross beta measurements (from Table 5-2) are compared to the arithmetic mean of their respective main contributors (sum of alpha emitters =  $^{241}\text{Am} + ^{239/240}\text{Pu}$ ; sum of beta emitters =  $2(^{90}\text{Sr}) + ^{137}\text{Cs}$ ). The comparison shows relatively good agreement in both cases, with RPDs of 12.1%.

Table 6-5. Alpha and Beta Energy Checks.

Calculation	Gross Alpha or Beta	RPD
<b>Total Alpha</b>		
$^{241}\text{Am} + ^{239/240}\text{Pu} = 1.16 \mu\text{Ci/g}$	1.31 $\mu\text{Ci/g}$	12.1%
<b>Total Beta</b>		
$2(^{90}\text{Sr}) + ^{137}\text{Cs} = 4.98 \mu\text{Ci/g}$	4.41 $\mu\text{Ci/g}$	12.1%

Figure 6-1. RSD Distributions for Variance Components Calculated from the Segment-Level Data.





This page intentionally left blank.

## 7.0 STATISTICAL QUALITY ASSURANCE TESTS

This section contains a summary of the various QA tests and measurements applied to the B-201 analytical results. These tests and measurements include the mass and charge balance, homogenization tests, spike recoveries, and method blanks.

### 7.1 MASS AND CHARGE BALANCE

The principal objective of a mass and charge balance is to determine if the measurements are self-consistent for the composite measurements. The values used in the calculation were obtained from Table 5-2. However, two very important constituents were not measured for this tank: hydroxide and oxygen. To rectify this deficiency, some assumptions had to be made about the missing constituents. Therefore, the mass and charge balances are directed toward filling in information about the missing constituents.

For the mass balance, it is assumed that unmeasured oxygen occurs within five oxy-anions,  $B_4O_7^{2-}$ ,  $PO_4^{3-}$ ,  $SeO_3^{2-}$ ,  $SiO_3^{2-}$ , and  $TeO_3^{2-}$ . Furthermore assume that all the boron, phosphorus, selenium, silicon, and tellurium measured in the core samples are present in these oxy-anion forms. To determine hydroxide, the charge balance was used: an appropriate amount of hydroxide was added to balance the charges.

Table 7-1 lists the metals used in the mass and charge balances, while Table 7-2 lists the anions. Concentrations of metals and anions are extracted from Table 5-2, which lists the best estimate of the tank contents. These tables also list the RSD associated with each estimate and the postulated charge. The RSDs are used to calculate the uncertainties associated with mass totals.

Table 7-1. Mass/Charge Balance for Metals. (2 pages)

Metal	Mass $\mu\text{g/g}$	RSD	Charge $\mu\text{mol/g}$	Metal	Mass $\mu\text{g/g}$	RSD	Charge $\mu\text{mol/g}$
Aluminum	3440	74	382.51	Antimony	37		0.91
Arsenic	60		2.38	Barium	86	38	1.26
Beryllium	4		0.82	Bismuth	94100	3	1350.85
Cadmium	5	6	0.09	Calcium	12200	58	608.78
Cerium	70	11	1.49	Chromium	3340	4	192.71
Cobalt	10	4	0.33	Copper	48	67	1.52
Dysprosium	29	31	0.54	Europium	7		0.15
Gadolinium	169	15	3.22	Iron	14400	21	773.54
Lanthanum	15100	10	326.13	Lead	1360	9	13.13
Lithium	15		2.15	Magnesium	1510	58	124.22
Manganese	19200	29	698.97	Molybdenum	19	4	1.19
Neodymium	22		0.46	Nickel	479	3	16.32

Table 7-1. Mass/Charge Balance for Metals. (2 pages)

Metal	Mass $\mu\text{g/g}$	RSD	Charge $\mu\text{mol/g}$	Metal	Mass $\mu\text{g/g}$	RSD	Charge $\mu\text{mol/g}$
Palladium	111		2.09	Potassium	5810	13	148.59
Rhodium	74		2.17	Ruthenium	37		1.10
Sodium	49600	23	2157.48	Strontium	923	5	21.07
Thallium	371		1.82	Thorium-232	594		10.24
Tin	596		20.09	Titanium	285	75	23.80
Tungsten	60		1.95	Uranium	156	100	3.93
Vanadium	16	38	1.56	Yttrium	8	18	0.28
Zinc	217	6	6.64	Zirconium	11	10	0.47

Table 7-2. Anions with postulated Oxy-anions.

Anion	Mass $\mu\text{g/g}$	RSD	Charge $\mu\text{mol/g}$	Postulated Oxygen Anion	$\mu\text{g/g}$	RSD
Boron	70	35	3.26	$B_4O_7^{2-}$	183	35
Chloride	1650	7	46.54			
Cyanide	3	28	0.13			
Fluoride	5830	2	306.87			
Nitrate	49300	1	795.16			
Nitrite	881	13	19.15			
Phosphorus	5450	14	527.93	$PO_4^{3-}$	11282	14
Selenium	67	9	3.38	$SeO_3^{2-}$	41	9
Silicon	29700	75	2466.16	$SiO_3^{2-}$	50787	75
Sulfate	348	44	10.88			
Tellurium	74		1.16	$TeO_3^{2-}$	28	

Table 7-3 shows the solubility of the phosphorus (as phosphate) by comparing the water-soluble portion to the total phosphate. The phosphate for this waste matrix is estimated to be 7% soluble (i.e., the majority of the phosphate is in the insoluble form).

Table 7-3. Phosphate Solubility.

Calculation	Phosphate Solubility
$\frac{\text{IC:W PO}_4^{3-} \text{ result}}{\text{ICP:F P result as PO}_4^{3-}} = \frac{1210}{16700} \times 100$	7.3%
$\frac{\text{ICP:W P result}}{\text{ICP:F P result}} = \frac{413}{5450} \times 100$	7.6%

In Table 7-2, the "unmeasured oxygen" has also been listed in the last three columns. Table 7-4 summarizes the mass and charge balances. The second and third columns in Table 7-4 list the total masses of metals, anions, and extra oxygen from Tables 7-1 and 7-2, along with the uncertainty associated with each total (expressed as an RSD). Total charges are listed again in the fourth column and from these total charges, the excess negative charge is determined. This excess negative charge has been assigned to hydroxide, and a charge balance determines the mass of hydroxide listed in the table.

Table 7-4. Summary of Mass/Charge Balance.

Source	Mass		Charge
	$\mu\text{g/g}$	RSD	$\mu\text{mol/g}$
Metal	224579	7	6907
Anion	93373	24	-4219
Oxygen	62320	61	
Hydroxide	45697		-2688
Subtotal	425969		0
Postulated $H_2O$	572820	11	
Measured $H_2O$	607000	3	
RPD ( $H_2O$ )	5.8%		
Estimated Waste Total (Subtotal + $H_2O$ )	1032969		
RPE (Total Waste)	3.3%		

Finally, postulated  $H_2O$  is determined by summing up the masses of metals, anions, extra oxygen, and hydroxide (in parts per million) and subtracting this number from a million. From Table 7-4, the postulated  $H_2O$  in the waste is 57%, and this number has an uncertainty of 11%. The measured percent water is 61% (determined from the average composite results given in Table 5-6), with an RSD of 3%. The disagreement is 4%, well

within the estimate uncertainties. As one can see from this mass balance, the assumptions made concerning hydroxide and oxygen seem to fit well with the data for the composite.

## 7.2 HOMOGENIZATION TESTS

Sample homogenization is a very important step in the process of making representative core composite samples. There were two homogenization steps for core samples from B-201. First, the segments from each core were homogenized; and second, homogenized waste from each segment was assembled and homogenized to create core composites. Samples were taken from the top and bottom of two segments per core (segments 3 and 7 from core 26 and segments 3 and 6 from core 27), and from the top and bottom of each core composite. Analytical results from these samples were used to determine if the sample homogenization was adequate. The segment level samples were prepared by acid digestion and chemically analyzed using ICP and GEA. The composite level samples were prepared using KOH/Ni fusion and chemically analyzed using ICP and GEA.

The analytical results from the top and bottom segment and composite samples (homogenization samples) were fit to the following nested random effects model:

$$Y_{ijk} = \mu + C_i + S_{ij} + H_{ijk} + E_{ijkl} \quad (3)$$

where:

$Y_{ijk}$  = The measured value of concentration of a constituent in segment  $j$  of core  $i$

$\mu$  = The mean concentration of the constituent

$C_i$  = The core sampled

$S_{ij}$  = The segment or composite from a core

$H_{ijk}$  = The location on the composite or segment (homogenization effect)

$E_{ijkl}$  = The analytical error.

The objective of the homogenization test is to determine if the variability in the results between sampling locations is greater than zero. This objective can be met using the results from an ANOVA on the random effects model.

The results from an ANOVA are presented in Table 7-5. The homogenization RSD (estimated variability between locations relative to the mean) is given, along with the p-value from the homogenization tests. Analytes with more than 75% of the analytical results below the detection limits were excluded from this analysis.

Table 7-5. Homogenization Test Results.

Composite Level Homogenization Tests (KOH/Ni Fusion ICP and GEA)									
Analyte	Homogenization		<DL	Obs	Analyte	Homogenization		<DL	Obs
	RSD(%)	p-value				RSD(%)	p-value		
Aluminum	14	0.001	0	16	Barium	12	0.203	0	16
Bismuth	0	0.875	0	16	Calcium	12	0.000	0	16
Chromium	0	0.799	0	16	Cobalt	0	0.474	10	16
Copper	32	0.201	0	16	Iron	9	0.030	0	16
Lanthanum	0	0.954	0	16	Lead	0	0.818	0	16
Magnesium	11	0.005	0	16	Manganese	0	0.945	0	16
Phosphorus	0	0.708	0	16	Silicon	13	0.035	0	16
Sodium	3	0.344	0	16	Strontium	0	0.925	0	16
Titanium	14	0.000	0	16	Vanadium	4	0.472	12	16
Zinc	0	0.676	0	16	Zirconium	5	0.472	12	16
Americium-241	28	0.029	0	16	Cesium-134	NA	NA	0	2
Cesium-137	93	0.181	0	16	Cobalt-60	0	0.651	4	12
Europium-154	0	0.787	0	12	Europium-155	NA	NA	0	8
Potassium-40	NA	NA	2	8					
Segment Level Homogenization Tests (Acid Digestion ICP and GEA)									
Analyte	Homogenization		<DL	Obs	Analyte	Homogenization		<DL	Obs
	RSD(%)	p-value				RSD(%)	p-value		
Aluminum	3	0.001	0	24	Barium	3	0.154	0	24
Bismuth	8	0.003	0	24	Boron	0	0.909	0	24
Calcium	2	0.217	0	24	Chromium	5	0.015	0	24
Copper	7	0.006	7	24	Iron	3	0.072	0	24
Lanthanum	7	0.002	0	24	Lead	4	0.151	4	24
Magnesium	0	0.775	0	24	Manganese	0	0.997	0	24
Phosphorus	4	0.029	0	24	Nickel	5	0.011	0	24
Potassium	1	0.305	3	24	Silicon	0	0.428	0	24
Sodium	6	0.003	0	24	Strontium	7	0.003	0	24
Titanium	1	0.177	1	24	Zinc	0	0.939	7	24
Americium-241	6	0.070	0	24	Cesium-134	14	0.217	7	15
Cesium-137	29	0.486	0	24	Cobalt-60	0	0.790	6	18
Europium-154	26	0.094	7	15	Europium-155	8	0.369	8	12

(p-value &lt; .05 indicates a significant RSD).

The homogenization tests on the composite level show that for 83% of the analytes tested, the variability due to homogenization cannot be distinguished from zero (99% significance level). In other words, the homogenization on the composite level is sufficient for 83% of the analytes tested. However, the core 26 report (Shaver 1993) indicates that many of the sample and duplicate RPDs are large (i.e., 10 to 30%, versus less than 10% at the segment level). These large RPDs may reduce the validity of the statement made above.

The homogenization tests on the segment level show that for 77% of the analytes tested, the variability due to homogenization cannot be distinguished from zero (99% significance level). For the other 23% of the analytes, the homogenization RSDs are relatively small (i.e., less than 10%). Even though variability due to homogenization is tested to be greater than zero (due to small analytical error), the variability is small enough to consider the homogenization adequate. The core 26 report (Shaver 1993) indicates again that there were large RPDs for several duplicate analyses. Due to the generally small homogenization RSDs, the large analytical error from these large RPDs does not affect conclusions about the homogenization as much as for the composites. In general, the homogenization on the segment level is considered adequate.

### 7.3 EVALUATION OF SPIKES AND BLANKS

Of the 7,598 observations in the B-201 data base, 2,480 are some form of spike or blank measurement run for QA purposes. In this section, we present a brief overview of these measurements. More detailed evaluations of the spikes and blanks can be found in the core reports.

Evaluation of blanks uncovered an important problem with the ICP fusion measurements on core 26. The blanks for many of the constituents were sometimes 50% of the measured value. When the blank results were compared to homogenization measurements on the same sample, it became apparent that the contamination being measured by the blanks was real.

Table 7-6 illustrates the problem. If one compares the homogenization measurements to the standard measurements, the results differ by approximately 58%, much more than the sample and duplicate replicates differ (about 5%). However, if one subtracts the blanks first, then the agreement becomes dramatically better (11%).

Table 7-6. Illustration of Contamination Problem for ICP fusion on Core 26.

Constituent	Standard Measure			Homogenization Measure			Adjusted Measure	
	Samp.	Dup.	Blank	Samp.	Dup.	Blank	Samp.	Dup.
Al	12324	13071	6115	6940	7183	<DL	6209	6956
B	14946	16567	15342	<DL	<DL	<DL	<DL	<DL
Ca	20207	20674	4065	19055	19537	<DL	16142	16609
Na	64039	68510	26897	41843	43726	<DL	37142	41613
Si	55255	59723	24351	29634	30620	<DL	30904	35372

Extracted from Tables 2-1a and 2-1c of core reports (Shaver 1993).

Values in table are for composite 1.

It is obvious that these measurements must be corrected for contamination. Blanks were therefore subtracted from the ICP fusion measurements. There are indications that other corrections might be in order. However, it has been the policy to make no such corrections for other tanks at Hanford, so corrections were limited to the ICP fusions for tank B-201.

### 7.3.1 Blank Measurements


Approximately 1,400 blank measurements were made on tank B-201 samples, the majority for the ICP analytic methods. Most blanks were below the detection limit (83%). Table 7-7 summarizes the blank measurements taken on tank B-201. The last column in this table shows what percentage of the actual measurement is represented by those blanks that were not below the detection limit. One would like the blanks to be a small percentage of the actual measurement, and Figure 7-1 graphically illustrates the sizes of the blank measurements above the detection limit. From this figure, it is obvious that some blanks are quite large.

Table 7-7. Summary of Blank Measurements.

Analyte: Sample Preparation	# Blanks < DL	# Blanks > DL	Median Blank Observed
AA (As):A	1	1	57
Ext Organic Halides	1	2	43
Alpha Radchem:F	3	11	1
Beta Radchem:F	4	6	17
GEA	3	2	10
GEA:A	10	7	14
GEA:F	12	13	25
GEA:W	0	3	3
ICP:A	405	101	2
ICP:F	216	52	24
ICP:W	176	8	3
IC:W	15	6	13
Liq Scintillation:W	0	3	35
Liq Scintillation:A	6	2	18
ISE:W	0	3	99
SVOA	195	1	15
VOA	93	9	0
Persulfate Oxidation:W	2	7	12
Beta Radchem:W	0	2	19



Figure 7-1. Boxplots of Blank/Actual for Each Analytical Method  
( $<DL$  Measurements Excluded).



### 7.3.2 Spike Measurements

Figure 7-2 shows the percent recovery distributions for spike measurements of each analysis type. The percent recovery is targeted to be between 75% and 125%, and this is generally the case for alpha and beta radiation chemistry and ion chromatography. However, as one can see from the box-plots, several analytical methods show much more variability than this. None of the measurements were corrected for recovery problems.

Figure 7-2. Boxplots % Recovery Calculated from Spike Measurements.




Table 7-8 summarizes the number of spike measurements that were outside the 75% to 125% recovery goals. As one can see, ICP acid stands out, with 152 measurements outside the desired range. Most recovery percents on ICP acid are quite small, about 4%.

Table 7-8. Summary of Recoveries Calculated from Spike Measurements.

Analyte: Preparation Method	Outside Range*	Within Range*
AA (As):A	2	2
AA (Sb):A	0	4
AA (Se):A	1	2
CVAA:A	1	0
Ext Organic Halides	1	2
Alpha Radchem:F	0	4
Beta Radchem:F	0	2
ICP:A	152	78
IC:W	3	27
Laser Fluorimetry:F	0	1
Liq Scintillation:W	0	1

\*Range = 75% to 125%.

### 7.3.3 Quality Assurance Flags

Hanford Analytical Services (HAS) reviewed all data and assigned QA flags to the results. Of the 7,598 measurements in the data set, HAS classified 920 (12%) as unusable and another 403 (55%) as suspect (i.e., suspect results are considered to be rough estimates only). In order to perform the analysis presented in this report, all data was used and none of the HAS-flagged data was deleted.

---

## 8.0 CONCLUSIONS AND RECOMMENDATIONS

The process waste history for tank B-201 is uncomplicated. Over its years of service, tank B-201 received most of its contents as discharges from the 224 Concentration Building, which had low enough fission product activity ( $< 0.001\%$  of that in the starting metal) to permit ground disposal after the waste was directed through a settling tank. The solid portion of the waste (106,000 liters [28,000 gallons]) is a dark brown to black sludge. There are approximately 3,800 liters (1,004 gallons) of supernate above the sludge.

Excluding water, the analytes found in highest concentration ( $> 10^4$  ppm) in B-201 core samples are bismuth, nitrate, sodium, silicon, manganese, lanthanum, iron, and calcium. The historical tank concentration estimates for B-201 were obtained from LANL, and supplemented by analytical results from a sampling event in 1978. Presently, the most significant difficulty in using the LANL estimates involves making comparisons with constituents that are not predicted in the waste, but which are actually present. Several constituents (such as aluminum) were predicted to be absent by LANL, but were actually found in significant concentration in the tank samples. Furthermore, there is no quantification of uncertainty with the LANL estimates at this time.

On the other hand, those constituents that LANL did predict were generally within one order of magnitude of the estimates obtained from the composite samples for B-201, making this an acceptable first estimate in the absence of any characterization information.

The ANOVA analysis of the core segment data showed that the vertical spatial variability is generally larger than horizontal variability, and laboratory-related variability is generally the smallest. However, analytical error is a significant contributor to the uncertainty about the mean for those analytes that are close to the detection limits.

From the composite data, the uncertainties in the best estimates are generally dominated by horizontal spatial variability. This has consequences for tank sampling: If more accurate estimates of the tank contents are required, then more core samples must be taken, through different risers. (Improvements in analytic procedures or in sampling methodology would not be adequate).

The QA tests show mixed results as to the usability of the analytical data from B-201 core samples. The mass/charge balance shows relatively good agreement between postulated and measured results. The homogenization test indicates that the waste samples from B-201 were generally mixed sufficiently to produce representative results. The analysis of spikes and blanks, however, reveals some problems with the data. Many of the spike recoveries (%) for ICP analyses are outside the acceptable range of  $\pm 25\%$ . It was also noted in Section 7.3.1 that many blank corrections had to be made for analyses performed by ICP fusion. HAS reviewed the B-201 core reports and flagged 12% of the data as unusable and 55% more as suspect.

B-201 is not on any of the watch lists (e.g., ferrocyanide or flammable gas), and therefore has no safety issues that need to be addressed.

This page intentionally left blank.

## 9.0 REFERENCES

- Anderson J. D., 1990, *A History of the 200 Area Tank Farms*, WHC-MR-0132, Westinghouse Hanford Company, Richland Washington.
- Brevick C. H., 1994, *Historical Tank Content Estimate for the Northeast Quadrant of the Hanford 200 East Areas*, WHC-SD-WM-ER-349, Rev. 0, Westinghouse Hanford Company, Richland, Washington.
- De Lorenzo D. S., J. H. Rutherford, D. J. Smith, D. B. Hiller, K. W. Johnson, and B. C. Simpson, 1994, *Tank Characterization Reference Guide*, WHC-SD-WM-TI-648, Rev. 0, Westinghouse Hanford Company, Richland, Washington.
- DOE, 1994, *Hanford Environmental Information System (HEIS)*, Tank Characterization Data (TCD) Subject Area, DOE/RL-93-24-8, Volume 8, U.S. Department of Energy, Richland Operations Office, Richland, Washington.
- Ecology, EPA, and DOE, 1993, *Hanford Federal Facility Agreement and Consent Order*, as amended, Washington State Department of Ecology, U.S. Environmental Protection Agency, and the U.S. Department of Energy, Olympia, Washington.
- HW-9191 DEL, 1948, Hanford Works Monthly Report, February 1948.
- HW-9595 DEL, 1948, Hanford Works Monthly Report, March 1948.
- Horton J. E., 1978, "Characterization of 200 Series Tanks," Internal Memo 60120-78-131, Rockwell Hanford Operations, Richland, Washington.
- Jungfleisch F. M., and B. C. Simpson, 1993, *A Preliminary Estimation of the Waste Inventories in Hanford Tanks Through 1980*, WHC-SD-WM-TI-057, Rev. 0-A, Westinghouse Hanford Company, Richland, Washington.
- PNL-ALO-225, 1990, *Measurement of pH in Aqueous Solutions*, Pacific Northwest National Laboratory Technical Procedure, Pacific Northwest National Laboratory, Richland, Washington.
- PNL-ALO-530, Rev. 0, 1989, *Particle Size Distribution By Laser Scanning (Time of Transition)*, Pacific Northwest National Laboratory Technical Procedure, Pacific Northwest National Laboratory, Richland, Washington.
- Shaver R. L., 1993, *PNL 325 Laboratories Single-Shell Tank Waste Characterization, Tank B-201 Cores 26 and 27*, WHC-SD-WM-DP-037, Westinghouse Hanford Company, Richland, Washington.

This page intentionally left blank.

## 10.0 BIBLIOGRAPHY

- Babad H., 1994, *Tank Safety Screening Data Quality Objective*, WHC-SD-WM-SP-004, Westinghouse Hanford Company, Richland, Washington.
- Bell K. E., 1993, *Tank Waste Remediation System Tank Waste Characterization Plan*, WHC-SD-WM-PLN-047, Rev. 1, Westinghouse Hanford Company, Richland, Washington.
- Hanlon B. M., 1992, *Tank Farm Surveillance and Waste Status Summary Report for September 1992*, WHC-EP-0182-39, Westinghouse Hanford Company, Richland, Washington.
- Hanlon B. M., 1993, *Tank Farm Surveillance and Waste Status Summary Report for November 1993*, WHC-EP-0182-68, Westinghouse Hanford Company, Richland, Washington.
- Huckaby J. L., 1992, *Characterization of Vapors in Single-Shell Tanks Scheduled for Rotary-Mode Sampling*, WHC-SD-WM-TI-536, Westinghouse Hanford Company, Richland, Washington.
- Winters W. I., L. Jensen, L. M. Sasaki, R. L. Weiss, J. F. Keller, A. J. Schmidt, and M. G. Woodruff, 1990, *Waste Characterization Plan for Hanford Site Single-Shell Tanks*, WHC-EP-0210, Rev. 1, Westinghouse Hanford Company, Richland, Washington.



This page intentionally left blank.

**APPENDIX A**

**TANK ENGINEERING DATA AND WASTE SUMMARY**

This page intentionally left blank.

APPENDIX A

TANK ENGINEERING DATA AND WASTE SUMMARY

Figure A-1. Top View of Tank B-201.




Table A-1. Engineering Data Summary of Tank B-201.

Tank Engineering Description	Tank Status as of 1994
Type: Single-shell tank	Watch List: None
Construction: 1943-1944	Interim Stabilized: 1981
In-Service: 1947	Interim Isolated: 1981
Out of Service: 1975	Contents: 224 waste*
Diameter: 6.1 m (20 ft)	Tank Integrity: Assumed leaker (1980) (4,500 L)
Depth: 7.6 m (25 ft)	
Nominal Capacity: 208,000 L (55,000 gal)	
Bottom Shape: Dished	
Hanford Coordinates: N45537.5, W52727.5	
Ventilation: Passive	

\*Non-complexed waste.

Table A-2. Inventory Summary for Tank B-201.

Physical Properties of Waste	
Total Waste: 110,000 L (29 000 gal)	Supernatant Volume: 3,800 L (1,000 gal)
Drainable Inter. Liquid: 11,400 L (3,000 gal)	Density: 1.25 g/mL
H <sub>2</sub> O Average: 60.6 %	Temperature Average: 17 °C (63 °F)
pH: 8.53	Maximum Exotherm: No Exotherms
Heat Load: 0.006 kW	
Chemical Properties of Waste	
Bismuth: 13,000 kg (9.45 wt %)	Calcium: 1,670 kg (1.22 wt %)
Nitrate: 6,770 kg (4.93 wt %)	Fluoride: 800 kg (0.58 wt %)
Sodium: 5,240 kg (3.82 wt %)	Potassium: 797 kg (0.58 wt %)
Silicon: 2,770 kg (2.02 wt %)	Phosphorus: 748 kg (0.55 wt %)
Manganese: 2,630 kg (1.92 wt %)	TOC: 71 kg (5.18e-02 wt %)
Lanthanum: 2,070 kg (1.51 wt %)	TIC: 287 kg (0.21 wt %)
Iron: 1,840 kg (1.34 wt %)	
Radionuclides in the Waste	
Total Plutonium: 156 Ci	Strontium-90: 287 Ci
Cesium-137: 110 Ci	Total Uranium 21.4 kg (1.56e-04 wt %)

**APPENDIX B**

**COMPOSITE ESTIMATES AND VARIABILITY SUMMARY**

This page intentionally left blank.

## APPENDIX B

## COMPOSITE ESTIMATES AND VARIABILITY SUMMARY

This section contains ANOVA table results for the composite data (including the drainable liquid). The most important value in this table is the average concentration estimate,  $\hat{\mu}$ , but the table also presents variance component estimates. The model used to produce these results is:

$$Y_{ijk} = \mu + C_i + S_{ij} + E_{ijk} \quad (4)$$

where:

$Y_{ijk}$  = The measured value of concentration of a constituent in replicate  $j$  of core  $i$

$\mu$  = The mean concentration of the constituent in the tank

$C_i$  = The deviation of concentration in core  $i$  from the mean value

$S_{ij}$  = The deviation of concentration in core replicates. (Two replicates were processed on each composite.)

$E_{ijk}$  = The analytical (lab) error in the measurements.

All RSDs presented in this appendix are in percent. The RSD associated with a variance component is the standard deviation of the component divided by  $\mu$ . The variance components listed in the table are as follows:  $\sigma_C$  is the standard deviation of  $C_i$ ;  $\sigma_S$  is the standard deviation of  $S_{ij}$ ; and  $\sigma_E$  is the analytical standard deviation.

Table B-1. Tank Concentration From Composite Samples. (8 pages)

Analyte	Analytical Method: Sample Preparation	Mean Concentration		ANOVA RSDs			Obs.	
		$\hat{\mu}$	RSD ( $\hat{\mu}$ )	$\sigma_c$	$\sigma_s$	$\sigma_e$	<DL	#
Anions								
		( $\mu\text{g/g}$ )						
Chloride	IC:W	1.65e+03	7	10	0	3	0	8
Cyanide	IC:W	3.49e+00	28	37	20	5	4	8
Fluoride	IC:W	5.83e+03	2	0	2	6	0	8
Nitrate	IC:W	4.93e+04	1	0	0	3	0	8
Nitrite	IC:W	8.81e+02	13	18	6	6	0	8
Phosphate	IC:W	1.21e+03	15	21	0	3	0	8
Phosphate	ICP:F	1.67e+04	NA	NA	NA	NA	NA	NA
Sulfate	IC:W	3.48e+02	44	62	NA	1	4	8



Table B-1. Tank Concentration From Composite Samples. (8 pages)

Analyte	Analytical Method: Sample Preparation	Mean Concentration		ANOVA RSDs			Obs.	
		$\hat{\mu}$	RSD ( $\hat{\mu}$ )	$\sigma_c$	$\sigma_c$	$\sigma_c$	<DL	#
Cations								
		( $\mu\text{g/g}$ )						
Aluminum	ICP:A	3.44e+03	74	102	30	27	0	13
Aluminum	ICP:F	3.91e+03	71	100	0	7	0	8
Aluminum	ICP:W	5.83e+01	56	79	13	11	0	13
Ammonia	ISE:W	1.04e+01	46	43	66	32	2	8
Antimony	AA (Sb):A	3.88e+01	NA	NA	NA	NA	7	8
Antimony	ICP:A	<3.71e+01	NA	NA	NA	NA	13	13
Antimony	ICP:F	<2.40e+02	NA	NA	NA	NA	8	8
Antimony	ICP:W	<8.04e+00	NA	NA	NA	NA	13	13
Arsenic	AA (As):A	4.50e-01	12	0	0	34	4	8
Arsenic	ICP:A	5.95e+01	NA	NA	NA	NA	12	13
Arsenic	ICP:F	4.11e+02	15	20	6	2	4	8
Arsenic	ICP:W	<1.29e+01	NA	NA	NA	NA	13	13
Barium	ICP:A	8.64e+01	38	53	15	6	0	13
Barium	ICP:F	1.67e+02	59	65	64	55	0	8
Barium	ICP:W	<1.61e+00	NA	NA	NA	NA	13	13
Beryllium	ICP:A	<3.71e+00	NA	NA	NA	NA	13	13
Beryllium	ICP:F	<2.40e+01	NA	NA	NA	NA	8	8
Beryllium	ICP:W	<8.04e-01	NA	NA	NA	NA	13	13
Bismuth	ICP:A	1.01e+05	13	17	0	15	0	13
Bismuth	ICP:F	9.45e+04	3	0	6	4	0	8
Bismuth	ICP:W	1.41e+01	22	30	0	20	6	13
Boron	ICP:A	7.05e+01	35	49	5	18	0	13
Boron	ICP:F	6.85e+02	87	102	58	112	3	8
Boron	ICP:W	5.66e+00	41	0	78	39	7	13
Cadmium	ICP:A	4.81e+00	6	0	5	18	8	13
Cadmium	ICP:F	5.27e+01	58	61	78	23	4	8
Cadmium	ICP:W	<8.04e-01	NA	NA	NA	NA	13	13
Calcium	ICP:A	1.22e+04	58	80	27	15	0	13
Calcium	ICP:F	1.04e+04	53	75	5	3	0	8
Calcium	ICP:W	5.06e+01	66	52	109	15	0	13
Cerium	ICP:A	6.96e+01	11	12	0	27	9	13
Cerium	ICP:F	<3.84e+02	NA	NA	NA	NA	8	8
Cerium	ICP:W	<1.29e+01	NA	NA	NA	NA	13	13
Chromium	ICP:A	3.34e+03	4	5	0	9	0	13
Chromium	ICP:F	3.38e+03	8	11	4	5	0	8
Chromium	ICP:W	8.59e+02	3	0	5	5	0	13

Table B-1. Tank Concentration From Composite Samples. (8 pages)

Analyte	Analytical Method: Sample Preparation	Mean Concentration		ANOVA RSDs			Obs.	
		$\bar{\mu}$	RSD ( $\bar{\mu}$ )	$\sigma_c$	$\sigma_c$	$\sigma_c$	<DL	#
Cobalt	ICP:A	9.60e+00	4	0	0	16	8	13
Cobalt	ICP:F	5.38e+01	8	0	5	20	5	8
Cobalt	ICP:W	<1.61e+00	NA	NA	NA	NA	13	13
Copper	ICP:A	4.82e+01	67	94	0	31	0	13
Copper	ICP:F	5.36e+01	21	28	0	17	0	8
Copper	ICP:W	<8.04e-01	NA	NA	NA	NA	13	13
Dysprosium	ICP:A	2.94e+01	31	38	0	56	9	13
Dysprosium	ICP:F	<9.60e+01	NA	NA	NA	NA	8	8
Dysprosium	ICP:W	<3.22e+00	NA	NA	NA	NA	13	13
Europium	ICP:A	<7.43e+00	NA	NA	NA	NA	13	13
Europium	ICP:F	<4.80e+01	NA	NA	NA	NA	8	8
Europium	ICP:W	<1.61e+00	NA	NA	NA	NA	13	13
Gadolinium	ICP:A	1.69e+02	15	7	0	32	9	13
Gadolinium	ICP:F	<9.60e+02	NA	NA	NA	NA	8	8
Gadolinium	ICP:W	<3.22e+01	NA	NA	NA	NA	13	13
Hexavalent Chromium	Calorimetric:W	7.47e+02	6	7	5	7	0	8
Iron	ICP:A	1.47e+04	32	44	5	7	0	13
Iron	ICP:F	1.34e+04	20	28	6	0	0	8
Iron	ICP:W	4.61e+00	28	36	19	16	0	13
Lanthanum	ICP:A	1.51e+04	10	13	0	13	0	13
Lanthanum	ICP:F	1.42e+04	4	0	7	4	0	8
Lanthanum	ICP:W	1.99e+01	60	83	20	29	3	13
Lead	ICP:A	1.36e+03	9	12	2	12	0	13
Lead	ICP:F	1.24e+03	26	27	3	2	0	8
Lead	ICP:W	<9.65e+00	NA	NA	NA	NA	13	13
Lithium	ICP:A	<1.49e+01	NA	NA	NA	NA	13	13
Lithium	ICP:F	<9.60e+01	NA	NA	NA	NA	8	8
Lithium	ICP:W	<3.22e+00	NA	NA	NA	NA	13	13
Magnesium	ICP:A	1.51e+03	58	80	24	13	0	13
Magnesium	ICP:F	1.20e+03	48	64	33	2	0	8
Magnesium	ICP:W	1.72e+01	NA	NA	NA	NA	11	13
Manganese	ICP:A	1.92e+04	29	32	0	64	0	13
Manganese	ICP:F	2.29e+04	6	8	6	4	0	8
Manganese	ICP:W	3.15e+00	31	36	33	20	0	13
Mercury	CVAA:A	5.99e-01	46	58	29	43	0	8
Molybdenum	ICP:A	1.91e+01	4	0	0	16	9	13
Molybdenum	ICP:F	<9.60e+01	NA	NA	NA	NA	8	8
Molybdenum	ICP:W	<3.22e+00	NA	NA	NA	NA	13	13

Table B-1. Tank Concentration From Composite Samples. (8 pages)

Analyte	Analytical Method: Sample Preparation	Mean Concentration		ANOVA RSDs			Obs.	
		$\bar{\mu}$	RSD ( $\bar{\mu}$ )	$\sigma_c$	$\sigma_c$	$\sigma_c$	<DL	#
Neodymium	ICP:A	<2.23e+01	NA	NA	NA	NA	13	13
Neodymium	ICP:F	<1.44e+02	NA	NA	NA	NA	8	8
Neodymium	ICP:W	<4.83e+00	NA	NA	NA	NA	13	13
Nickel	ICP:A	4.79e+02	3	0	0	11	0	13
Nickel	ICP:F	4.29e+02	21	NA	NA	22	0	4
Nickel	ICP:W	4.03e+00	24	33	0	22	9	13
Palladium	ICP:A	<1.11e+02	NA	NA	NA	NA	13	13
Palladium	ICP:F	<7.20e+02	NA	NA	NA	NA	8	8
Palladium	ICP:W	<2.41e+01	NA	NA	NA	NA	13	13
Phosphorus	ICP:A	5.79e+03	20	28	10	6	0	13
Phosphorus	ICP:F	5.45e+03	14	18	10	4	0	8
Phosphorus	ICP:W	4.13e+02	17	24	4	7	0	13
Potassium	ICP:A	5.81e+03	13	17	9	6	0	13
Potassium	ICP:F	8.24e+03	7	NA	NA	14	0	4
Potassium	ICP:W	4.65e+03	8	10	6	5	0	13
Rhodium	ICP:A	<7.43e+01	NA	NA	NA	NA	13	13
Rhodium	ICP:F	<4.80e+02	NA	NA	NA	NA	8	8
Rhodium	ICP:W	<1.61e+01	NA	NA	NA	NA	13	13
Ruthenium	ICP:A	<3.71e+01	NA	NA	NA	NA	13	13
Ruthenium	ICP:F	<2.40e+02	NA	NA	NA	NA	8	8
Ruthenium	ICP:W	<8.04e+00	NA	NA	NA	NA	13	13
Selenium	AA (Se):A	<1.53e+00	NA	NA	NA	NA	8	8
Selenium	ICP:A	6.68e+01	9	8	0	24	9	13
Selenium	ICP:F	<3.60e+02	NA	NA	NA	NA	8	8
Selenium	ICP:W	<1.21e+01	NA	NA	NA	NA	13	13
Silicon	ICP:A	2.42e+03	21	29	7	4	0	13
Silicon	ICP:F	2.02e+04	63	89	0	8	0	8
Silicon	ICP:W	6.29e+02	29	38	20	12	0	13
Silver	ICP:A	1.23e+01	20	27	9	14	5	13
Silver	ICP:F	4.72e+01	7	6	7	13	6	8
Silver	ICP:W	<1.61e+00	NA	NA	NA	NA	13	13
Sodium	ICP:A	3.79e+04	9	12	5	4	0	13
Sodium	ICP:F	3.82e+04	2	0	0	6	0	8
Sodium	ICP:W	3.09e+04	3	2	4	4	0	13
Strontium	ICP:A	9.23e+02	5	5	0	11	0	13
Strontium	ICP:F	8.97e+02	6	7	6	3	0	8
Strontium	ICP:W	9.38e-01	9	0	17	3	1	13
Tellurium	ICP:A	<7.43e+01	NA	NA	NA	NA	13	13
Tellurium	ICP:F	<4.80e+02	NA	NA	NA	NA	8	8
Tellurium	ICP:W	<1.61e+01	NA	NA	NA	NA	13	13

Table B-1. Tank Concentration From Composite Samples. (8 pages)

Analyte	Analytical Method: Sample Preparation	Mean Concentration		ANOVA RSDs			Obs.	
		$\bar{\mu}$	RSD ( $\bar{\mu}$ )	$\sigma_c$	$\sigma_c$	$\sigma_c$	<DL	#
Thallium	ICP:A	<3.71e+02	NA	NA	NA	NA	13	13
Thallium	ICP:F	<2.40e+03	NA	NA	NA	NA	8	8
Thallium	ICP:W	<8.04e+01	NA	NA	NA	NA	13	13
Tin	ICP:A	5.96e+02	NA	NA	NA	NA	11	13
Tin	ICP:F	<3.84e+03	NA	NA	NA	NA	8	8
Tin	ICP:W	<1.29e+02	NA	NA	NA	NA	13	13
Titanium	ICP:A	2.85e+02	75	104	29	27	0	13
Titanium	ICP:F	4.25e+02	68	96	0	3	0	8
Titanium	ICP:W	<8.04e-01	NA	NA	NA	NA	13	13
Tungsten	ICP:A	5.96e+01	NA	NA	NA	NA	12	13
Tungsten	ICP:F	<3.84e+02	NA	NA	NA	NA	8	8
Tungsten	ICP:W	<1.29e+01	NA	NA	NA	NA	13	13
Uranium	ICP:A	8.78e+02	10	10	0	26	9	13
Uranium	ICP:F	<4.80e+03	NA	NA	NA	NA	8	8
Uranium	ICP:W	<1.61e+02	NA	NA	NA	NA	13	13
Uranium	Laser Fluorimetry:F	1.56e+02	100	141	0	7	0	8
Vanadium	ICP:A	1.59e+01	38	52	21	15	5	13
Vanadium	ICP:F	<4.80e+01	NA	NA	NA	NA	8	8
Vanadium	ICP:W	<1.61e+00	NA	NA	NA	NA	13	13
Yttrium	ICP:A	8.19e+00	18	21	0	37	9	13
Yttrium	ICP:F	<4.80e+01	NA	NA	NA	NA	8	8
Yttrium	ICP:W	<1.61e+00	NA	NA	NA	NA	13	13
Zinc	ICP:A	2.17e+02	6	0	8	14	0	13
Zinc	ICP:F	2.32e+02	19	0	0	54	0	8
Zinc	ICP:W	<3.22e+00	NA	NA	NA	NA	13	13
Zirconium	ICP:A	1.07e+01	10	0	18	15	7	13
Zirconium	ICP:F	5.30e+01	17	22	13	11	4	8
Zirconium	ICP:W	<1.61e+00	NA	NA	NA	NA	13	13
Organics								
		( $\mu\text{g/g}$ )						
1,2,4-Trichlorobenzene	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
1,2-Dichlorobenzene	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
1,3-Dichlorobenzene	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
1,4-Dichlorobenzene	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
2,4,5-Trichlorophenol	SVOA	<2.40e+02	NA	NA	NA	NA	8	8
2,4,6-Trichlorophenol	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
2,4-Dichlorophenol	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
2,4-Dimethylphenol	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
2,4-Dinitrophenol	SVOA	<2.40e+02	NA	NA	NA	NA	8	8

Table B-1. Tank Concentration From Composite Samples. (8 pages)

Analyte	Analytical Method: Sample Preparation	Mean Concentration		ANOVA RSDs			Obs.	
		$\hat{\mu}$	RSD ( $\hat{\mu}$ )	$\sigma_c$	$\sigma_c$	$\sigma_c$	<DL	#
2,4-Dinitrotoluene	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
2,6-Dinitrotoluene	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
2-Chloronaphthalene	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
2-Chlorophenol	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
2-Methylnaphthalene	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
2-Methylphenol	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
2-Nitroaniline	SVOA	<2.40e+02	NA	NA	NA	NA	8	8
2-Nitrophenol	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
3,3'-Dichlorobenzidine	SVOA	<9.69e+01	NA	NA	NA	NA	8	8
3-Nitroaniline	SVOA	<2.40e+02	NA	NA	NA	NA	8	8
4,6-Dinitro-o-cresol	SVOA	<2.40e+02	NA	NA	NA	NA	8	8
4-Bromophenylphenyl ether	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
4-Chloro-3-methylphenol	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
4-Chloroaniline	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
4-Methylphenol	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
4-Nitroaniline	SVOA	<2.40e+02	NA	NA	NA	NA	8	8
4-Nitrophenol	SVOA	<2.40e+02	NA	NA	NA	NA	8	8
Acenaphthene	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
Acenaphthylene	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
Anthracene	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
Benzo(a)anthracene	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
Benzo(a)pyrene	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
Benzo(b)fluoranthene	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
Benzo(ghi)perylene	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
Benzo(k)fluoranthene	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
Benzoic acid	SVOA	<2.40e+02	NA	NA	NA	NA	8	8
Benzyl alcohol	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
Bis(2-chloroethyl) ether	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
Bis(2-chloroisopropyl)	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
Butylbenzylphthalate	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
Chrysene	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
Di-n-butylphthalate	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
Di-n-octylphthalate	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
Dibenz[a,h]anthracene	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
Dibenzofuran	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
Diethylphthalate	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
Dimethyl phthalate	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
Dodecane	SVOA	2.85e+02	8	0	11	17	0	8
Fluoranthene	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
Fluorene	SVOA	<4.80e+01	NA	NA	NA	NA	8	8

Table B-1. Tank Concentration From Composite Samples. (8 pages)

Analyte	Analytical Method: Sample Preparation	Mean Concentration		ANOVA RSDs			Obs.	
		$\bar{\mu}$	RSD ( $\bar{\mu}$ )	$\sigma_c$	$\sigma_c$	$\sigma_c$	<DL	#
Hexachlorobenzene	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
Hexachlorobutadiene	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
Hexachloroethane	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
Indeno(1,2,3-cd)pyrene	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
Isophorone	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
N-Nitrosodiphenylamine	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
Naphthalene	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
Nitrobenzene	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
Pentachlorophenol	SVOA	<2.40e+02	NA	NA	NA	NA	8	8
Pentadecane	SVOA	4.10e+01	37	50	19	11	0	8
Phenanthrene	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
Phenol	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
Pyrene	SVOA	<4.80e+01	NA	NA	NA	NA	8	8
Tetradecane	SVOA	1.03e+03	28	38	15	13	0	8
Total carbon	Persulfate Oxidation:D	5.59e+03	50	71	0	8	0	8
Total carbon	Persulfate Oxidation:W	2.55e+03	12	16	8	5	0	8
Total inorganic carbon	Persulfate Oxidation:D	3.14e+03	32	45	7	3	0	8
Total inorganic carbon	Persulfate Oxidation:W	2.09e+03	16	21	11	10	0	8
Total organic carbon	Persulfate Oxidation:D	2.36e+03	73	103	8	21	0	8
Total organic carbon	Total Organic Halides	6.28e+02	9	NA	NA	18	0	4
Tridecane	SVOA	9.29e+02	7	0	9	15	0	8
Physical Properties								
		(%)						
Weight percent solids	Percent Solids:D	3.93e+01	3	NA	NA	8	0	8
Radionuclides								
		( $\mu$ Ci/g)						
Americium-241	Alpha Radchem:F	2.87e-02	4	0	0	11	0	8
Americium-241	GEA:F	3.10e-02	4	0	3	11	0	8
Carbon-14	Liq Scintillation:W	3.16e-04	NA	NA	NA	NA	7	8
Cesium-134	GEA:F	2.38e-03	NA	NA	NA	NA	0	3
Cesium-137	GEA:F	8.00e-01	27	27	27	34	0	8
Cesium-137	GEA:W	4.69e-02	NA	NA	NA	NA	0	4
Cobalt-60	GEA:F	1.96e-03	75	105	0	29	3	8
Curium-243/244	Alpha Radchem:F	1.64e-03	21	NA	NA	41	0	4
Europium-154	GEA:F	4.38e-03	51	67	37	13	2	8
Europium-155	GEA:F	3.28e-03	NA	NA	NA	NA	4	5
Gross alpha	Alpha Radchem:F	1.31e+00	18	26	0	5	0	8
Gross alpha	Alpha Radchem:W	4.71e-04	21	NA	NA	30	0	4
Gross beta	Beta Radchem:F	4.41e+00	28	25	0	62	0	8
Gross beta	Beta Radchem:W	5.34e-02	16	NA	NA	4	0	4

Table B-1. Tank Concentration From Composite Samples. (8 pages)

Analyte	Analytical Method: Sample Preparation	Mean Concentration		ANOVA RSDs			Obs.	
		$\hat{\mu}$	RSD ( $\hat{\mu}$ )	$\sigma_c$	$\sigma_c$	$\sigma_c$	<DL	#
Neptunium-237	Alpha Radchem:F	<1.24e-04	NA	NA	NA	NA	8	8
Nickel-59	Beta Radchem:A	6.86e-06	22	29	0	25	6	8
Nickel-63	Liq Scintillation:A	1.88e-04	25	0	0	71	0	8
Plutonium-238	Alpha Radchem:F	6.90e-03	98	139	0	16	0	4
Plutonium-239/240	Alpha Radchem:F	1.13e+00	30	42	0	8	0	4
Potassium-40	GEA:W	1.24e-03	NA	NA	NA	NA	0	2
Strontium-90	Beta Radchem:F	2.09e+00	51	68	32	12	0	8
Technetium-99	Beta Radchem:F	1.94e-03	NA	NA	NA	NA	8	8
Total alpha*	Alpha Radchem:F	1.14e+00	NA	NA	NA	NA	0	4
Tritium	Liq Scintillation:W	2.05e-02	78	108	33	7	0	8
		(%)						
Uranium-234	Mass Spectrometry:F	5.40e-03	6	0	0	17	0	8
Uranium-235	Mass Spectrometry:F	6.91e-01	0	1	0	0	0	8
Uranium-236	Mass Spectrometry:F	5.20e-03	6	2	0	16	0	8
Uranium-238	Mass Spectrometry:F	9.93e+01	0	0	0	0	0	8
Plutonium-238	Mass Spectrometry:F	4.87e-03	15	0	0	43	0	8
Plutonium-239	Mass Spectrometry:F	9.84e+01	0	0	0	0	0	8
Plutonium-240	Mass Spectrometry:F	1.55e+00	1	1	0	2	0	8
Plutonium-241	Mass Spectrometry:F	1.30e-02	16	0	0	46	0	8
Plutonium-242	Mass Spectrometry:F	3.84e-03	43	42	50	4	0	8

\*Total alpha emitted from  $^{238}\text{Pu}$ ,  $^{239}\text{Pu}$ ,  $^{240}\text{Pu}$ ,  $^{241}\text{Pu}$ .

**APPENDIX C**

**SEGMENT-LEVEL ESTIMATES AND VARIABILITY SUMMARY**



This page intentionally left blank.

## APPENDIX C

## SEGMENT-LEVEL ESTIMATES AND VARIABILITY SUMMARY

This appendix contains estimates of concentration computed from segment-level data. One can also compute vertical profiles of the waste from the segment-level data. The basic results of the ANOVA fits are presented in the table, while the vertical profiles are presented graphically.

The model used to produce these results is:

$$Y_{ijk} = \mu + C_i + S_j + CS_{ij} + E_{ijk} \quad (5)$$

where  $i$  is the core,  $j$  is the segment, and  $k$  is the sample replicate of the measurement. The term  $\mu$  represents the tank average and the other terms represent deviations from the tank average. Each deviation in the above model has an associated variability that is measured by the ANOVA procedure. These sources of variability are denoted by  $\sigma_C$ ,  $\sigma_S$ , etc., and are expressed as a percent RSD (the sigma divided by  $\mu$ ).

Table C-1. Tank Concentrations from Segment Samples. (3 pages)

Constituent	Mean Concentration			ANOVA RSD's				Obs.	
	$\hat{\mu}$		RSD	$\sigma_C$	$\sigma_S$	$\sigma_{CS}$	$\sigma_E$	<DL	#
<b>Anions</b>									
Phosphorus	4.71e+03	μg/g	12	0	13	13	4	0	24
<b>Metals</b>									
Aluminum	1.27e+03	μg/g	87	5	106	89	3	0	24
Barium	6.13e+01	μg/g	9	6	0	15	6	0	24
Bismuth	9.15e+04	μg/g	29	3	40	8	7	0	24
Boron	4.01e+03	μg/g	91	0	32	177	6	0	24
Calcium	6.38e+03	μg/g	75	0	103	35	4	0	24
Chromium	3.34e+03	μg/g	30	15	35	23	4	0	24
Copper	2.49e+01	μg/g	71	30	89	48	12	7	24
Iron	1.13e+04	μg/g	32	6	45	0	5	0	24
Lanthanum	1.35e+04	μg/g	25	0	34	12	4	0	24
Lead	2.69e+02	μg/g	57	5	80	8	8	4	24
Magnesium	7.84e+02	μg/g	65	0	85	46	3	0	24
Manganese	1.66e+04	μg/g	33	33	26	0	68	0	24
Molybdenum	3.09e+01	μg/g	26	34	8	0	36	20	24
Nickel	4.31e+02	μg/g	27	19	33	0	5	0	24

Table C-1. Tank Concentrations from Segment Samples. (3 pages)


Constituent	Mean Concentration			ANOVA RSD's				Obs.	
	$\hat{\mu}$		RSD	$\sigma_c$	$\sigma_s$	$\sigma_{CS}$	$\sigma_E$	<DL	#
Potassium	2.90e+03	$\mu\text{g/g}$	15	6	20	0	16	3	24
Silicon	5.07e+03	$\mu\text{g/g}$	69	20	46	118	7	0	24
Silver	1.52e+01	$\mu\text{g/g}$	28	36	12	0	37	20	24
Sodium	3.40e+04	$\mu\text{g/g}$	10	3	13	2	5	0	24
Strontium	9.02e+02	$\mu\text{g/g}$	31	0	44	7	4	0	24
Titanium	1.14e+02	$\mu\text{g/g}$	90	30	95	110	1	1	24
Uranium	1.47e+03	$\mu\text{g/g}$	33	40	14	17	41	21	24
Zinc	4.66e+01	$\mu\text{g/g}$	31	17	40	0	10	7	24
Zirconium	1.60e+01	$\mu\text{g/g}$	23	13	16	35	31	20	24
Organics									
Hexamethyl-disiloxane	2.14e+04	$\mu\text{g/kg}$	26	NA	35	NA	35	0	5
Methoxytri-methylsilane	1.43e+05	$\mu\text{g/kg}$	22	NA	35	NA	24	0	6
Toluene	5.08e+03	$\mu\text{g/kg}$	23	NA	38	NA	13	0	6
Trimethyl-silanol	1.32e+05	$\mu\text{g/kg}$	28	NA	43	NA	35	0	6
Physical Properties									
Centrifuged solids density	1.47e+00	$\text{g/ml}$	7	NA	9	NA	6	0	9
Centrifuged supernate density	1.05e+00	$\text{g/ml}$	3	NA	0	NA	8	0	9
Critical flow rate-2in	3.80e+01	$\text{gal/min}$	39	NA	54	NA	20	0	6
Critical flow rate-3in	7.55e+01	$\text{gal/min}$	38	NA	53	NA	21	0	6
Critical velocity-2in	3.66e+00	$\text{ft/sec}$	38	NA	52	NA	20	0	6
Critical velocity-3in	3.27e+00	$\text{ft/sec}$	38	NA	52	NA	21	0	6
Density	1.25e+00	$\text{g/ml}$	2	0	0	0	11	0	26
Flow behavior index	8.62e-01	UNITLESS	4	NA	0	NA	11	0	6
Particle size number density mean	1.26e+00	microns	5	NA	0	NA	14	0	8
Particle size volume density mean	2.92e+01	microns	21	NA	0	NA	60	0	8
Reynolds number-2in	8.26e+03	UNITLESS	1	NA	0	NA	3	0	6
Reynolds number-3in	1.04e+04	UNITLESS	3	NA	0	NA	6	0	6
Settled solids	7.69e+01	%	11	NA	0	NA	33	0	9
Shear strength	1.33e+04	$\text{dynes/cm}^2$	5	NA	6	NA	5	0	3
Volume % centrifuged solids	5.42e+01	%	20	NA	0	NA	61	0	9
Weight loss %	4.33e+01	%	17	NA	17	NA	53	0	16
Weight % centrifuged solids	5.93e+01	%	17	NA	0	NA	52	0	9
Weight % solids	4.64e+01	%	18	20	0	22	36	0	32
Yield point	3.84e+00	Pa	55	NA	76	NA	24	0	6

Table C-1. Tank Concentrations from Segment Samples. (3 pages)


Constituent	Mean Concentration			ANOVA RSD's				Obs.	
	$\hat{\mu}$		RSD	$\sigma_c$	$\sigma_s$	$\sigma_{CS}$	$\sigma_E$	<DL	#
Radionuclides									
Americium-241	2.83e-02	$\mu\text{Ci/g}$	41	3	48	46	9	0	24
Cesium-134	1.62e-03	$\mu\text{Ci/g}$	13	0	7	0	44	7	15
Cesium-137	1.45e-01	$\mu\text{Ci/g}$	57	17	78	0	42	0	24
Cobalt-60	1.90e-03	$\mu\text{Ci/g}$	29	26	23	22	34	6	18
Europium-154	3.32e-03	$\mu\text{Ci/g}$	31	34	16	25	34	7	17
Europium-155	4.15e-03	$\mu\text{Ci/g}$	23	26	15	0	25	8	12

The pages that follow contain plots only for the best method of analysis. In other words, only our best estimate for each available constituent is presented. Each plot describes an individual analyte, and shows its vertical profile  $\mu + S_j$  and confidence bounds, as well as the core profiles  $\mu + C_i + S_j + CS_{ij}$  and their confidence bounds.


Figure C-1. Plots for Best Method of Analysis. (page 1 of 14)




(1)



(2)




(3)




(4)


Figure C-1. Plots for Best Method of Analysis. (page 2 of 14)




(5)



(6)




(7)



(8)


Figure C-1. Plots for Best Method of Analysis. (page 3 of 14)

Critical flow rate-3 inch




(9)

Critical velocity - 2 inch




(10)

Critical velocity - 3 inch




(11)

Calcium




(12)


Figure C-1. Plots for Best Method of Analysis. (page 4 of 14)




(13)



(14)




(15)




(16)




Figure C-1. Plots for Best Method of Analysis. (page 5 of 14)




(17)



(18)




(19)




(20)


Figure C-1. Plots for Best Method of Analysis. (page 6 of 14)




(21)



(22)




(23)




(24)


Figure C-1. Plots for Best Method of Analysis. (page 7 of 14)




(25)



(26)




(27)




(28)


Figure C-1. Plots for Best Method of Analysis. (page 8 of 14)




(29)



(30)




(31)




(32)


Figure C-1. Plots for Best Method of Analysis. (page 9 of 14)




(33)



(34)




(35)




(36)


Figure C-1. Plots for Best Method of Analysis. (page 10 of 14)




(37)



(38)




(39)




(40)


Figure C-1. Plots for Best Method of Analysis. (page 11 of 14)




(41)



(42)




(43)



(44)


Figure C-1. Plots for Best Method of Analysis. (page 12 of 14)

Particle size probability volume density mean




(45)

Settled solids




(46)

Shear strength



(47)


Centrifuged supernate density




(48)




Figure C-1. Plots for Best Method of Analysis. (page 13 of 14)




(49)



(50)




(51)




(52)

Figure C-1. Plots for Best Method of Analysis. (page 14 of 14)



(53)



(54)

This page intentionally left blank.

**APPENDIX D**

**RAW DATA SET SUMMARY**

This page intentionally left blank.

**APPENDIX D****RAW DATA SET SUMMARY**

This appendix describes the format of the B-201 data set used to produce the results discussed in this report. The data set contains chemical measurements made by the 325-A Laboratory on B-201 core samples. The data was originally downloaded from the Tank Characterization Database (TCD). The following changes were made to the data set in preparation for the various statistical analyses:

1. The Na<sub>2</sub>O<sub>2</sub> Fusion ICP analyses were removed for all constituents with the exception of nickel and potassium.
2. The KOH Fusion ICP analyses were removed from the data set for nickel and potassium.
3. Only 17 of the original 40 TCD fields remain in the data set. The 17 fields remaining in the data set are those that are pertinent to the data analysis.
4. Any sample result that was below the detection limit was replaced with the detection limit value if it was available.
5. All of the TCLP results from the Acid Digestion ICP analysis method were removed to avoid confusion with the standard Acid Digestion ICP analyses.
6. The blanks were subtracted from all constituent sample results for the ICP Fusion analysis method.
7. The organics results were converted from parts per billion to parts per million.

An electronic ASCII copy of the B-201 data set is available upon request. This data set does not include any of the QA data (i.e., matrix spikes and method blanks). The B-201 data set is 5,109 records in length. Table D-1 describes the contents of each field. Reference DOE 1994 contains more information on the format of the data in the TCD.

Table D-1. Description of B-201 Data Set Fields.

Field	Description
1	Core Number
2	Segment or Composite Number
3	Analytical Method Name
4	Phase of the Waste Sample (i.e., Solid or Liquid)
5	Sample Location (TOP and BOTTOM are homogenization samples and TOTAL is the standard sample)
6	Sample ID Number (assigned by the 325-A Laboratory)
7	Dilution Factor
8	Sample Batch Number
9	Table and Page Number in the Validation Report that contains the sample results
10	Constituent name
11	Measured Sample Result
12	Result Type (e.g., Primary Result, Duplicate Result)
13	Result Units
14	Detection Limit
15	Detection Limit Units
16	Data Quality Flags assigned by Hanford Analytical Services (HAS)
17	Field indicating if a result is above the detection limit (T = above DL, F = below DL)

Table D-2 contains an example of three records from the B-201 dataset.

Table D-2. Excerpt from B-201 Raw Data Set.

Field 1	Field 2	Field 3	Field 4	Field 5
Field 6	Field 7	Field 8	Field 9	Field 10
Field 11	Field 12	Field 13	Field 14	Field 15
Field 16	Field 17			
core26	3	Extraction Organic (VOA)	S	TOTAL
BLANK	1.0		PG.145	Tetrachloroethane
3.800000e+06	PRIMARY_RESULT	UG/G	NA	
UDR	F			
core26	3	Acid Digestion ICP	S	TOP
9203238A	10.0	21	Pg 67, Table 2-2c	Tellurium
2.087700e+02	DUPLICATE RESULT	UG/G	208.77000	UG/G
U	F			
core27	Compl	Fusion ICP	S	BOTTOM
9210669H1B	2.0	49	Pg 353, Table 2-1b	Tellurium
4.293200e+02	DUPLICATE RESULT	UG/G	429.32000	UG/G
U	F			

**APPENDIX E**

**RHEOLOGICAL PROPERTIES TABLES AND PLOTS**



This page intentionally left blank.

---

---

## APPENDIX E

### RHEOLOGICAL PROPERTIES TABLES AND PLOTS

This appendix contains an excerpt from Shaver 1993 on the rheological properties measured on tank B-201, core 26 sample. Shear strength, waste flow properties, and settling behavior are discussed and tables and plots are given.

The shear strength of the three segment samples was measured in at least duplicate. The average values for the shear strength of segments 2, 5, and 8 are reported in Table 5-5.

Shear stress as a function of shear rate was run in duplicate at ambient temperature for each of the segment materials. The shear stress exceeded the maximum value of system being used for this measurement (8500 Pa or 85,000 dynes/cm<sup>2</sup>). The cone was being rotated at a significantly larger rate than was used for the shear strength measurement; therefore, the shear stress measured would be higher than the shear strength of the material. Some drying of the sample may also have occurred on the plate, causing the shear strength to be higher than expected. Due to drying of the samples at 95 °C (203 °F), the shear stress of the samples as a function of shear rate could not be measured on the as-received samples or 1:1 dilution at this temperature.

Rheological properties were measured in duplicate on the dilutions of segments 2, 5, and 8 at ambient temperature. A single measurement of shear stress as a function of shear rate was run at a 3:1 dilution at 95 °C. Only one measurement was made because the sample was drying too quickly to make a duplicate measurement which accurately represented the viscosity of the sample.

The 1:1 dilution samples exhibit yield pseudoplastic behavior, and the data was fit to a yield power law expression. The equation to fit this data is given by Equation 6. The parameters from this fit were input into a model developed by Hanks to predict the flow properties for non-Newtonian fluids. The data-obtained from this model is PNNL QA Impact Level III. The data obtained includes critical velocity for turbulent flow and critical Reynolds number. This data and the fit parameters for each sample are given in Tables E-1 and E-2.

$$\tau = \tau_y + K\dot{\gamma}^n \quad (6)$$

where:

$\tau$	=	Shear stress
$\tau_y$	=	Yield point
$K$	=	Consistency parameter
$\gamma$	=	Shear rate
$n$	=	Flow behavior index.

Table E-1. Power Law Curve Fit Parameters of 1:1 Dilution Samples.

Segment	Temp. (°C)	Run	Yield Point (Pa)	Consistency Factor (Pa sec)	Flow Behavior Index
2	30	1	1.16	6.51e-03	0.92
		2	2.29	1.61e-02	0.81
5	30	2	4.77	8.89e-03	1.00
		3	6.38	2.34e-02	0.85
8	29	1	9.53	2.82e-02	0.86
		2	6.60	6.66e-02	0.73

Table E-2. Flow Properties of 1:1 Dilution Samples.

Segment	Temp (°C)	Run	Pipe (in.)	Critical Velocity (ft/sec)	Critical Flow Rate (gal/min)	Critical Reynolds Number
2	30	1	2	1.9	19	8,500
			3	1.7	38	10,800
		2	2	2.6	27	8,100
			3	2.3	54	9,900
5	30	1	2	4.1	43	8,600
			3	3.6	84	11,300
		2	2	4.7	49	8,100
			3	4.2	97	10,000
8	30	1	2	5.9	61	8,000
			3	5.3	122	9,900
		2	2	5.4	57	6,100
			3	4.9	113	7,200

The 3:1 dilutions also exhibit yield pseudoplastic behavior with a yield point of less than 0.5 Pa. The viscosity and yield point of the samples was so low that no attempt was made to model the data. At shear rates greater than  $100 \text{ s}^{-1}$ , the viscosity of the 3:1 dilution samples was less than 5 cP. The viscosity of the 3:1 dilution decreases significantly with increasing temperature.

Plots of shear stress and viscosity as a function of shear rate for the dilutions are shown in Figures E-1, E-2, and E-3.




Figure E-2. Settling Behavior of Segment 5 (Core 26).





Figure E-3. Settling Behavior of Segment 8 (Core 26).



This page intentionally left blank.

# DISTRIBUTION SHEET

To Distribution	From Data Assessment and Interpretation	Page 4 of 4
		Date 06/03/96
Project Title/Work Order Tank Characterization Report for Single-Shell Tank 241-B-201, WHC-SD-WM-ER-550, Rev. 0		EDT No. EDT-615398
		ECN No. N/A

Name	MSIN	Text With All Attach.	Text Only	Attach./Appendix Only	EDT/ECN Only
------	------	-----------------------	-----------	-----------------------	--------------

Westinghouse Hanford Company continued

W. C. Miller	R1-30	X
C. T. Narquis	T6-16	X
D. E. Place	H5-27	X
D. A. Reynolds	R2-11	X
L. M. Sasaki (2)	R2-12	X
L. W. Shelton, Jr.	H5-49	X
B. C. Simpson	R2-12	X
G. L. Troyer	T6-50	X
M. S. Waters	S6-30	X
L. R. Webb	T6-06	X
K. A. White	S5-13	X
<del>TFIC (Tank Farm Information Center)</del>	<del>R1-20</del>	<del>X</del>
Central Files (1) <i>plus original</i>	A3-88	X
EDMC	H6-08	X
ERC (Environmental Resource Center)	R1-51	X
<del>OSTI (2)</del>	<del>A3-36</del>	<del>X</del>
TCRC (10)	R2-12	X



# DISTRIBUTION SHEET

To Distribution	From Data Assessment and Interpretation	Page 3 of 4
		Date 06/03/96
Project Title/Work Order Tank Characterization Report for Single-Shell Tank 241-B-201, WHC-SD-WM-ER-550, Rev. 0		EDT No. EDT-615398
		ECN No. N/A

Name	MSIN	Text With All Attach.	Text Only	Attach./ Appendix Only	EDT/ECN Only
------	------	-----------------------------	-----------	------------------------------	-----------------

## ONSITE

### Department of Ecology

A. B. Stone	B5-18	X			
-------------	-------	---	--	--	--

### Department of Energy - Richland Operations

J. F. Thompson	S7-54	X			
W. S. Liou	S7-54	X			
N. W. Willis	S7-54	X			

### ICF-Kaiser Hanford Company

R. L. Newell	S3-09	X			
--------------	-------	---	--	--	--

### Pacific Northwest Laboratory

N. G. Colton	K3-75	X			
J. R. Gormsen	K7-28				X
S. A. Hartley	K5-12	X			
J. G. Hill	K7-94	X			
G. J. Lumetta	P7-25	X			
A. F. Noonan	K9-81	X			

### Westinghouse Hanford Company

H. Babad	S7-14	X			
D. A. Barnes	R1-80	X			
G. R. Bloom	H5-61	X			
J. M. Conner	R2-12	X			
W. L. Cowley	A3-37	X			
G. L. Dunford	S7-81	X			
E. J. Eberlein	R2-12				X
D. B. Engelman	R1-49	X			
J. S. Garfield	H5-49	X			
J. D. Guberski	R2-06				X
D. L. Herting	T6-09	X			
G. Jansen	H6-33	X			
G. D. Johnson	S7-15	X			
T. J. Kelley	S7-21	X			
N. W. Kirch	R2-11	X			
M. J. Kupfer	H5-49	X			
J. E. Meacham	S7-15	X			

# DISTRIBUTION SHEET

To Distribution	From Data Assessment and Interpretation	Page 2 of 4
		Date 06/03/96
Project Title/Work Order Tank Characterization Report for Single-Shell Tank 241-B-201, WHC-SD-WM-ER-550, Rev. 0		EDT No. EDT-615398
		ECN No. N/A

Name	MSIN	Text With All Attach.	Text Only	Attach./ Appendix Only	EDT/ECN Only
------	------	-----------------------------	-----------	------------------------------	-----------------

SAIC  
20300 Century Boulevard, Suite 200-B  
Germantown, MD 20874

H. Sutter X

555 Quince Orchard Rd., Suite 500  
Gaithersburg, MD 20878

P. Szerszen X

Los Alamos Laboratory  
CST-14 MS-J586  
P. O. Box 1663  
Los Alamos, NM 87545

S. F. Agnew (4) X

Los Alamos Technical Associates

T. T. Tran B1-44 X

Ogden Environmental  
101 East Wellsian Way  
Richland, WA 99352

R. J. Anema X

CH2M Hill  
P. O. Box 91500  
Bellevue, WA 98009-2050

M. McAfee X

Tank Advisory Panel  
102 Windham Road  
Oak Ridge, TN 37830

D. O. Campbell X

# DISTRIBUTION SHEET

To	From	Page 1 of 4	
Distribution	Data Assessment and Interpretation	Date	06/03/96
Project Title/Work Order Tank Characterization Report for Single-Shell Tank 241-B-201, WHC-SD-WM-ER-550, Rev. 0		EDT No.	EDT-615398
		ECN No.	N/A

Name	MSIN	Text With All Attach.	Text Only	Attach./ Appendix Only	EDT/ECN Only
------	------	-----------------------------	-----------	------------------------------	-----------------

## OFFSITE

Sandia National Laboratory  
P.O. Box 5800  
MS-0744, Dept. 6404  
Albuquerque, NM 87815

D. Powers X

Nuclear Consulting Services Inc.  
P. O. Box 29151  
Columbus, OH 43229-01051

J. L. Kovach X

Chemical Reaction Sub-TAP  
P.O. Box 271  
Lindsborg, KS 67456

B. C. Hudson X

Tank Characterization Panel  
Senior Technical Consultant  
Contech  
7309 Indian School Road  
Albuquerque, NM 87110

J. Arvisu X

U. S. Department of Energy - Headquarters  
Office of Environmental Restoration and Waste Management EM-563  
12800 Middlebrook Road  
Germantown, MD 20874

J. A. Poppitti X

Jacobs Engineering Group  
3250 W. Clearwater  
Kennewick, WA 99336

X